



- NOTES:**
1. THE EXISTING FIBER OPTIC AND TRACER CABLE FROM GOUGAR ROAD TO THE I-80 WEST RAMP SHALL BE PULLED BACK TO THE FAR HANDHOLE ON THE EAST LEG AND STORED IN IT FOR REUSE ON THE PROPOSED INTERCONNECT. THIS WORK WILL BE PAID FOR IN THE UNIT BID PRICE FOR PULL AND REINSTALL FIBER OPTIC CABLE.
  2. THE FIBER OPTIC AND TRACER CABLE BETWEEN WASHINGTON STREET AND GOUGAR ROAD SHALL BE REMOVED. THIS WORK WILL BE PAID FOR IN THE UNIT BID PRICE FOR REMOVE ELECTRIC CABLE FROM CONDUIT.
  3. A TEMPORARY RADIO INTERCONNECT SHALL BE INSTALLED TO MAINTAIN THE EXISTING INTERCONNECT DURING CONSTRUCTION. EQUIPMENT SHALL BE INSTALLED AT WASHINGTON STREET AND I-80 WEST RAMP ALONG WITH GOUGAR ROAD FOR THIS TEMPORARY INTERCONNECT TO MAINTAIN A WORKING ORDER. (SEE SPECIAL PROVISIONS FOR MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION AND TEMPORARY TRAFFIC SIGNAL INSTALLATION.)

INTERCONNECT TO I-80 EB RAMPS

THE TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "EAGLE" TO MATCH THE EXISTING ADJACENT SYSTEM.

**LEGEND**

	EXISTING RIGHT-OF-WAY
--	-----------------------

**SEC Group, Inc.**  
 1500 North LaSalle  
 Chicago, IL 60610  
 Tel: (773) 424-2000  
 Fax: (773) 424-2001  
 www.secgroupinc.com

USER NAME = RBest	DESIGNED - MJF	REVISED -
PLOT SCALE = 1" = 50'	DRAWN - MJF	REVISED -
PLOT DATE = 11/8/2011	CHECKED - APS	REVISED -
	DATE - 11/8/11	REVISED -

**ILLINOIS DEPARTMENT OF TRANSPORTATION  
 PROPOSED ROADWAY IMPROVEMENTS  
 C.H. 52 (GOUGAR ROAD) AT U.S. ROUTE 30**

**INTERCONNECT PLAN  
 U.S. ROUTE 30  
 WASHINGTON STREET TO I-80 WEST RAMPS**

SCALE: 1" = 50'	SHEET NO. OF SHEETS	STA. TO STA.
-----------------	---------------------	--------------

F.A.U. RTE.	SECTION NO.	COUNTY	TOTAL SHEETS	SHEET NO.
367	07-00154-11-TL	WILL	70	47
CONTRACT NO. 63597				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				