

**SUMMARY OF QUANTITIES**

SP	SPECIALTY TEM	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003	TRAFFIC SIGNALS 0021	TRANEES 0042
		20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	60	60		
		20100500	TREE REMOVAL, ACRES	ACRE	0.25	0.25		
		20101000	TEMPORARY FENCE	FOOT	700	700		
		20200100	EARTH EXCAVATION	CU YD	16,222	16,222		
		20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	225	225		
		21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	673	673		
		21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	8,330	8,330		
		21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	4,592	4,592		
		21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	250	250		
		25000210	SEEDING, CLASS 2A	ACRE	2.00	2.00		
		25000310	SEEDING, CLASS 4	ACRE	1.00	1.00		
		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	245	245		
		25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	245	245		
		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	245	245		
		25100630	EROSION CONTROL BLANKET	SQ YD	13,569	13,569		
		28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	286	286		
*		28000305	TEMPORARY DITCH CHECK	FOOT	204	204		
		28000400	PERIMETER EROSION BARRIER	FOOT	4,967	4,967		
		28000500	INLET AND PIPE PROTECTION	EACH	27	27		
		28000510	INLET FILTERS	EACH	8	8		
		28001100	TEMPORARY EROSION CONTROL BLANKET	SQ YD	6,785	6,785		
		35501321	HOT-MIX ASPHALT BASE COURSE, 9 1/4"	SQ YD	6,620	6,620		
		35600713	HOT-MIX ASPHALT BASE COURSE WIDENING, 9 1/4"	SQ YD	385	385		
		40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	7,460	7,460		
		40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	169	169		
		40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	448	448		
		40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1,817	1,817		
		40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2,137	2,137		
		44000100	PAVEMENT REMOVAL	SQ YD	1,146	1,146		
		44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	979	979		
		44003100	MEDIAN REMOVAL	SQ FT	1,377	1,377		
		44004250	PAVED SHOULDER REMOVAL	SQ YD	3,584	3,584		
		44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	50	50		
		44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	50	50		
		44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	50	50		
		44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	50	50		
		44213200	SAWCUTS	FOOT	3,359	3,359		
		44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3,359	3,359		
		48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	1,078	1,078		
		48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	3,502	3,502		

PLAN	SURVEYED	DATE
	PLOTTED	
	CHECKED	
	BY	
	NOTE BOOK NO.	
	PAID FILE NAME	

PROFILE	SURVEYED	DATE
	PLOTTED	
	CHECKED	
	BY	
	NOTE BOOK NO.	
	STRUCTURE NOTATIONS CHKD	

FILE NAME = D:\157207-SHT-S00-01.DGN

USER NAME = melopez  
 PLOT SCALE = #SCALE#  
 PLOT DATE = 11/29/2011

DESIGNED - ML  
 DRAWN - BH  
 CHECKED - DW  
 DATE - 04-04-11

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**RANDALL ROAD AT US ROUTE 20 (FOOTHILL ROAD)  
 SUMMARY OF QUANTITIES**

SCALE: NTS SHEET NO. 1 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
336	06-00345-00-CH	KANE	92	5
CONTRACT NO. 63623				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				