

**GENERAL NOTES**

THE CONTRACTOR WILL BE REQUIRED TO COMPLY WITH ALL STATE REGULATIONS REGARDING AIR, WATER AND NOISE POLLUTION. HE WILL NOT BE ALLOWED TO BUILD FIRES ON THE SITE.

ALL CONSTRUCTION PERSONNEL WILL BE REQUIRED TO WEAR FLUORESCENT ORANGE VESTS AND HARD HATS AT ALL TIMES WHILE ON THE CONSTRUCTION SITE. COMPLIANCE WITH THIS REQUIREMENT SHALL BE CONSIDERED INCLUDED IN THE COST OF THE CONTRACT.

IT IS THE CONTRACTOR'S RESPONSIBILITY TO ASCERTAIN EXISTING FIELD CONDITIONS BEFORE BIDDING ON THIS PROJECT, SPECIFICALLY AS THEY RELATE TO THE LUMP SUM PAY ITEMS.

THE LOCATIONS OF KNOWN UTILITIES AS SHOWN ON THE PLANS ARE APPROXIMATE AND DOES NOT GUARANTEE THEIR ACCURACY. THE CONTRACTOR SHALL VERIFY THE LOCATION OF THESE UTILITIES AND THE EXISTENCE AND LOCATION OF ANY UTILITY NOT SHOWN ON THE PLANS.

THE CONTRACTOR SHALL NOTIFY THE UTILITIES AT LEAST TEN (10) DAYS PRIOR TO ANY CONSTRUCTION IN THE AREA AND SHALL COMPLY WITH ALL RESTRICTIONS FOR EQUIPMENT MOVEMENTS AND CLEARANCES AS REGARDS TO THEIR FACILITIES.

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR MUST CALL J.U.L.I.E. AT 1-800-832-0123 FOR FIELD LOCATIONS OF BURIED ELECTRICAL, TELEPHONE, GAS FACILITIES, AND ALL PUBLIC UTILITIES. A 48 HOUR NOTIFICATION IS REQUIRED.

<b>ELECTRIC</b>	<b>GAS</b>	<b>TELEPHONE</b>
COMMONWEALTH EDISON ATTN: MR. TIM COSLET 1910 SOUTH BRIGGS STREET JOLIET, IL. 60433-9599 (815) 724-5010	NICOR GAS ATTN: MS CONNIE LANE 1844 FERRY ROAD NAPERVILLE, IL. 60563 (630) 983-8676	A.T.&T. ATTN: MR. DENNIS VOLTAREL 65 WEST WEBSTER STREET JOLIET, IL. 60431 (815) 774-6762

<b>CABLE T.V.</b>	<b>WATER &amp; SEWER</b>
COMCAST CABLE COMMUNICATIONS ATTN: MS. MARY STEFAN 688 INDUSTRIAL DRIVE ELMHURST, IL. 60126 (630) 600-6346	CITY OF JOLIET ATTN: MS. SHARON BURGIE PUBLIC WORKS AND UTILITIES 921 E. WASHINGTON ST. JOLIET, IL. 60433-1267

THE CONTRACTOR SHALL USE ALL NECESSARY PRECAUTIONS AND PROTECTIVE MEASURES REQUIRED TO MAINTAIN EXISTING UTILITIES, SEWER AND APPURTENANCES THAT MUST BE KEPT IN OPERATION. IN PARTICULAR, THE CONTRACTOR WILL TAKE ADEQUATE MEASURES TO PREVENT THE UNDERMINING OF UTILITIES AND SEWERS WHICH ARE STILL IN SERVICE.

IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTIES AT ALL TIMES DURING CONSTRUCTION OF THE PROJECT.

IF ANY LOOSE MATERIAL IS DEPOSITED DURING CONSTRUCTION OPERATIONS IN THE FLOW LINE OF DITCHES, GUTTERS OR DRAINAGE STRUCTURES SO THAT IT RESTRICTS THE NATURAL FLOW OF WATER, IT SHALL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. AT THE CONCLUSION OF CONSTRUCTION OPERATIONS, ALL DRAINAGE STRUCTURES SO AFFECTED SHALL BE FREE FROM ALL DEBRIS. THIS WORK SHALL BE CONSIDERED INCLUDED IN THE COST OF THIS CONTRACT.

ALL FRAMES, GRATES, SIGNS, FENCES AND DELINEATORS, NEW OR EXISTING, DAMAGED BY THE CONTRACTOR DURING CONSTRUCTION SHALL BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE.

THE FOLLOWING SHALL BE NOTIFIED BY THE CONTRACTOR AT LEAST TEN (10) DAYS PRIOR TO THE START OF CONSTRUCTION:

JOLIET TWP. H.S. CENTRAL CAMPUS	815-727-6890
JOLIET TWP. H.S. WEST CAMPUS	815-727-6950
LARAWAY SCHOOL BUS BARN	815-727-5196
JOLIET - EAST FIRE DISTRICT	815-723-1504
WILL CO. SHERIFF	815-727-6191

NO WORK SHALL COMMENCE UNTIL TRAFFIC CONTROL REQUIREMENTS ARE MET.





THE CROSS SECTIONS INDICATE THE FINISHED GRADE OF TOPSOIL.

TOPSOIL SHALL NOT BE STOCKPILED WITHIN THE LIMITS OF CONSTRUCTION. THE LOCATIONS OF TOPSOIL TO BE STOCKPILED WITHIN THE RIGHT-OF-WAY MUST BE APPROVED BY THE ENGINEER.

THE FOLLOWING RATES OF APPLICATION HAVE BEEN ASSUMED IN CALCULATING PLAN QUANTITIES:

GRANULAR MATERIALS	2.05 TONS/CU YD
BITUMINOUS MATERIALS PRIME COAT	0.08 GAL/SQ YD DR
	0.375 GAL/SQ YD
AGGREGATE PRIME COAT	0.002 TONS/SQ YD
HOT-MIX ASPHALT SURFACE COURSE	112 LBS/SQ YD/INCH
HOT-MIX ASPHALT BINDER COURSE	112 LBS/SQ YD/INCH
NITROGEN FERTILIZER NUTRIENT	60 LBS/ACRE (SODDING) 90 LBS/ACRE (SEEDING)
PHOSPHOROUS FERTILIZER NUTRIENT	60 LBS/ACRE (SODDING) 90 LBS/ACRE (SEEDING)
POTASSIUM FERTILIZER NUTRIENT	60 LBS/ACRE (SODDING) 90 LBS/ACRE (SEEDING)
SHORT TERM PAVEMENT MARKING	10 FT/100 FT OF FINAL APPLICATION
LEVELING BINDER (MACHINE METHOD)	112 LBS/SQ YD/INCH
MULCH	2 TONS/ACRE

**LEGEND**

	PROPOSED PCC SIDEWALK
	PROPOSED HOT-MIX ASPHALT ENTRANCE
	PERIMETER EROSION BARRIER
	TEMPORARY EROSION CONTROL SEEDING (ENTIRE DISTURBED AREA AS DIRECTED BY THE ENGINEER.)

**INDEX OF SHEETS**

- 1 COVER SHEET
- 2 INDEX OF SHEETS, LIST OF STANDARDS, GENERAL NOTES & LEGEND
- 3 SUMMARY OF QUANTITIES
- 4 TYPICAL SECTIONS
- 5 SCHEDULES OF QUANTITIES
- 6 PLAN AND PROFILE
- 7 DETOUR PLAN
- 8 ENTRANCE & SPECIAL DETAILS
- 9-34 STRUCTURE PLANS
- 35-36 CROSS SECTIONS

**TIE POINT COORDINATES**

TYPE	STA.	NORTHING	EASTING
P.O.T.	7+00.00	9,616.25	9,983.61
P.I.	8+92.20	9,808.45	9,982.55
P.I.	11+05.38	10,021.62	9,982.79
P.O.T.	12+50.00	10,166.20	9,986.57

**LIST OF STANDARDS**

STANDARD NO.	DESCRIPTION
000001-06	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
280001-06	TEMPORARY EROSION CONTROL SYSTEMS
420401-08	BRIDGE APPROACH PAVEMENT CONNECTOR
515001-03	NAME PLATE FOR BRIDGES
606001-04	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
609006-05	BRIDGE APPROACH PAVEMENT (DRAIN DETAIL)
630001-10	STEEL PLATE BEAM GUARDRAIL
630301-05	SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
631031-10	TRAFFIC BARRIER TERMINAL, TYPE 6
635011-02	REFLECTOR MARKER AND MOUNTING DETAILS
701901-02	TRAFFIC CONTROL DEVICES
780001-03	TYPICAL PAVEMENT MARKINGS

FILE NAME = v:\2882\2882g\001.dgn	USER NAME = bdeoraene	DESIGNED -	REVISED - 10/20/2011	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>JOLIET ST. INDEX OF SHEETS, LIST OF STANDARDS, GENERAL NOTES &amp; LEGEND</b>	RTE. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE = 1:800 / / IN.	DRAWN -	REVISED -			N/A	07-10117-00-BR	WILL	36	2	
	PLOT DATE = 10/21/2011	CHECKED -	REVISED -			SCALE: N/A		SHEET NO. 1 OF 1 SHEETS		STA. N/A TO STA. N/A	
		DATE -	REVISED -			CONTRACT NO. 63642					
						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					