

SUMMARY OF QUANTITIES

SPECIALTY ITEM &/OR SPECIAL PROVISION	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		SPECIALTY ITEM &/OR SPECIAL PROVISION	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
					0004	0014						0004	0014	
					ROADWAY	STRUCTURE						ROADWAY	STRUCTURE	
	20200100	EARTH EXCAVATION	CU YD	62	62			52000110	PREFORMED JOINT STRIP SEAL	FOOT	85		85	
SP	20400800	FURNISHED EXCAVATION	CU YD	9	9			52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12		12	
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	242	242			52100520	ANCHOR BOLTS, 1"	EACH	24		24	
	25000210	SEEDING, CLASS 2A	ACRE	0.5	0.5			54210182	PIPE ELBOW, 12"	EACH	2	2		
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45	45			54215547	METAL END SECTIONS 12"	EACH	2	2		
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45	45			58700300	CONCRETE SEALER	SQ FT	400		400	
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45	45			60103500	PIPE DRAINS, CORRUGATED STEEL 12"	FOOT	32	32		
	25100115	MULCH, METHOD 2	ACRE	1	1			60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	184	184		
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	200	200			60900140	TYPE B INLET BOX, STANDARD 609006	EACH	2	2		
	28000400	PERIMETER EROSION BARRIER	FOOT	258	258			SI	63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1	
	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1164	1164			SI	63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1	1	
	35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	331	331			SI	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	
SP	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	114	114			SI	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	530	530			SP	63200310	GUARDRAIL REMOVAL	FOOT	34	34	
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	127	127			SP, SI	63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	41.5	41.5	
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	3	3				67100100	MOBILIZATION	L SUM	1	1	
	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	34	34			BDE, SI	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	110	110	
	42001300	PROTECTIVE COAT	SQ YD	32	32			SP, SI	78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16	
	42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	533	533			SP, SI	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	574	574			GBSP	X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	36		36
	44000100	PAVEMENT REMOVAL	SQ YD	797	797			SP	X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1	
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	242	242			GBSP	Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	12		12
	48101200	AGGREGATE SHOULDERS, TYPE B	TON	66	66			GBSP, SI	Z0007112	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES	L SUM	1		1
	48203035	HOT-MIX ASPHALT SHOULDERS, 9 1/2"	SQ YD	52	52			GBSP, SI	Z0010501	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1		1
	50102400	CONCRETE REMOVAL	CU YD	13.3		13.3			Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
	50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1		1		SP	Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	2		2
	50200100	STRUCTURE EXCAVATION	CU YD	48		48		BDE	Z0076600	TRAINEES *	hour	500		500
	50300225	CONCRETE STRUCTURES	CU YD	35.4		35.4								
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	328.8		328.8								
	50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	16900		16900								
	50500505	STUD SHEAR CONNECTORS	EACH	2160		2160								
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	77900		77900								
	50800515	BAR SPLICERS	EACH	74		74								
SI	50900105	ALUMINUM RAILING, TYPE L	FOOT	143		143								
	51500100	NAME PLATES	EACH	1		1								

SP=SPECIAL PROVISION SI=SPECIALTY ITEM BDE=BUREAU OF DESIGN AND ENVIRONMENT GBSP=GUIDE BRIDGE SPECIAL PROVISION

*(TRAINEES) CONSTRUCTION CODE IS "0042"