

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL	ROADWAY 0028	BRIDGE 0028	NON-PARTICIPATING 0043
20101000	TEMPORARY FENCE	FOOT	720	720		
20200100	EARTH EXCAVATION	CU YD	7	7		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	375	375		
25100630	EROSION CONTROL BLANKET	SQ YD	668	668		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	330	330		
28000400	PERIMETER EROSION BARRIER	FOOT	465	465		
28100107	STONE RIPRAP, CLASS A4	SQ YD	16		16	
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	200	200		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	520	520		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	78	78		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	21	21		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	14	14		
44000100	PAVEMENT REMOVAL	SQ YD	197	197		
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1	
50102400	CONCRETE REMOVAL	CU YD	30.1		30.1	
50200100	STRUCTURE EXCAVATION	CU YD	27		27	
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	23		23	
50201101	COFFERDAM (TYPE 1) (LOCATION - 1)	EACH	1		1	
50201102	COFFERDAM (TYPE 1) (LOCATION - 2)	EACH	1		1	

CODE NUMBER	ITEM	UNIT	TOTAL	ROADWAY 0028	BRIDGE 0028	NON-PARTICIPATING 0043
50300100	FLOOR DRAINS	EACH	4		4	
50300225	CONCRETE STRUCTURES	CU YD	36.1		36.1	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	128.1		128.1	
50300300	PROTECTIVE COAT	SQ YD	435		435	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	24,770		24,770	
50800515	BAR SPLICERS	EACH	92		92	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	16		16	
67100100	MOBILIZATION	L SUM	1	1		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	55		55	
Δ Z0076600	TRAINEES	HOUR	500	500		
• X0323444	DECORATIVE STEEL RAILING	FOOT	328		328	
X0325352	PIPE SUPPORT	EACH	31			31
X0325728	REMOVE AND RE-ERECT MORTARED STONE WALL	SQ FT	194	194		
X0326500	BRIDGE OPERATION AND MAINTENANCE DURING CONSTRUCTION	L SUM	1	1		
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	27		27	
X5000010	POST-TENSIONING SYSTEM	L SUM	1		1	
50800630	MECHANICAL SPLICERS	EACH	48		48	
XX008065	TRAFFIC CONTROL AND PROTECTION FOR BICYCLE PATH DETOUR	L SUM	1	1		

• SPECIALTY ITEM
Δ 0042



USER NAME = #USER#
PLOT SCALE = #SCALE#
PLOT DATE = #DATE#

DESIGNED - SDH
DRAWN - JJO/JWK
CHECKED - MSW
DATE - 10/17/11

REVISED - DJM 11/07/11
REVISED -
REVISED -
REVISED -

**GENEVA PARK DISTRICT
GENEVA, ILLINOIS**

**SUMMARY OF QUANTITIES
ISLAND PARK NORTH BRIDGE**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	06-P4005-00-BR	KANE	42	3
CONTRACT NO. 63643				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				