

EARTHWORK				
LOCATION	EARTH EXCAVATION	TOTAL EXCAVATION ADJUSTED FOR 25% SHRINKAGE	EMBANKMENT	BALANCE WASTE (+) SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
STA 11+00 TO STA 12+00.75	3	2	0	2
STA 13+83.25 TO STA 14+50	4	3	1	2
TOTAL	7	5	1	4

AGGREGATE FOR TEMPORARY ACCESS	
LOCATION	TON
STA 10+98 TO 14+52	520
TOTAL	520

EROSION CONTROL			
LOCATION	EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING	PERIMETER EROSION BARRIER
	SQ YD	POUND	FOOT
STA 11+00 TO STA 12+00.75 LT	178	90	98
STA 11+00 TO STA 12+00.75 RT	231	110	174
STA 13+83.25 TO STA 14+50 LT	122	60	130
STA 13+83.25 TO STA 14+50 RT	137	70	63
TOTAL	668	330	465

TEMPORARY FENCE	
LOCATION	FOOT
STA 11+07 TO 14+52 (LT SIDE)	357
STA 10+98 TO 11+52 (RT SIDE)	363
TOTAL	720

PAVEMENT REMOVAL	
LOCATION	SQ YD
STA 11+00 TO STA 12+00.75	122
STA 13+83.25 TO STA 14+50	75
TOTAL	197

PAVING MATERIALS			
LOCATION	AGG BASE CSE TY B 6"	BIT MATLS (PRIME COAT)	HMA SURF CSE, MIX "D", N50
	SQ YD	GALLON	TON
STA 11+00 TO STA 12+00.75	125	49	14
STA 13+83.25 TO STA 14+50	75	29	7
TOTAL	200	78	21

BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	
LOCATION	SQ FT
STA 12+00.75 TO 12+06.75	7
STA 13+77.35 TO 13+83.25	7
TOTAL	14

GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	
LOCATION	SQ YD
STA 10+98 TO 14+73	375
TOTAL	375

REMOVE AND RE-ERECT MORTARED STONE WALL	
LOCATION	SQ FT
STA 12+08 LT	27
STA 12+10 RT	120
STA 13+80 LT	27
STA 13+80 RT	20
TOTAL	194



USER NAME = #USER#
 PLOT SCALE = #SCALE#
 PLOT DATE = #DATE#

DESIGNED - SDH
 DRAWN - JJO/JWK
 CHECKED - MSW
 DATE - 10/17/11

REVISED -
 REVISED -
 REVISED -
 REVISED -

**GENEVA PARK DISTRICT
 GENEVA, ILLINOIS**

**SCHEDULE OF QUANTITIES
 ISLAND PARK NORTH BRIDGE**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	06-P4005-00-BR	KANE	42	5
CONTRACT NO. 63643				
FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT				