

SUMMARY OF QUANTITIES

CODE OR ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CHURCH ROAD & IL 56	IL RTE 56 (BUTTERFIELD ROAD)	MESA LANE	WIND ENERGY PASS	PINE STREET	WILSON STREET	HUBBARD AVENUE	FABYAN PARKWAY	CHERRY LANE	ROAD WEATHER INFORMATION SYSTEM	IL RTE 38 (STATE STREET)	IL RTE 38 @ GLENGARRY DR.	IL RTE 38 @ EAST SIDE DR.	EVERILL ROAD/EVERILL CIRCLE	DIVISION STREET	LEGACY BOULEVARD	TYLER ROAD	DUKANE DRIVE/OHIO AVENUE	IL RTE 64 (MAIN STREET)	FOXFIELD ROAD/FOXFIELD DRIVE	FOX CHASE/ORANGE & BLACK DRIVE	DUNHAM ROAD & ARMY TRAIL ROAD	DUNHAM ROAD & STERNS ROAD	INTERCONNECT KIRK ROAD	INTERCONNECT DUNHAM ROAD	INTERCONNECT IL RTE 38			
				0021																												
20200100	EARTH EXCAVATION	CU YD	26	2			2		2			2		2	2	2		2			2	2		2	2	2						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	302	23.2			23.2		23.2			23.2		23.2	23.2	23.2		23.2			23.2	23.2		23.2	23.2	23.2						
67100100	MOBILIZATION	L SUM	1																													
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1																													
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1																													
△ 70102665	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606, SPECIAL	L SUM	1																													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1																													
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1																													
80500010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	7												1		1			1	1		1	1	1							
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	3						1	1		1																				
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	17,652												10					10	10		10	10	10			5176	12416			
81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	275																												275	
81300945	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 24" X 24" X 8"	EACH	2																												2	
81400100	HANDHOLE	EACH	33																												8	25
81400300	DOUBLE HANDHOLE	EACH	1																												1	
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	22	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1					
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	7				1								1		1			1	1		1	1								
85700500	FULL-ACTUATED CONTROLLER IN EXISTING CABINET	EACH	1										1																			
86200200	UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	14	1			1	1	1	1		1		1	1			1		1	1		1	1	1							
87300010	GROUNDING EXISTING HANDHOLE FRAME AND COVER	EACH	40				4		4	4		6						4		3	4		4	4	3							
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	484				113		82	94		42						28		25	25		25	25	25							
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	3,728				393		352	431		372						431		255	410		443	400	241							
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	24												4					4	4		4	4	4							
87800205	MODIFY EXISTING TYPE "D" FOUNDATION	EACH	1							1																						
87900200	DRILL EXISTING HANDHOLE	EACH	13												1					1	1		1	1				3	2	3		
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1				1																									
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	5				5																									
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1				1																									

△ DENOTES ITEMS REQUIRING SPECIAL PROVISIONS
 * UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA. INCLUDES THE FOLLOWING ITEMS REFERENCED IN THE PLAN SHEET SCHEDULE OF QUANTITIES:
 -CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL
 -CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL
 -TRENCH AND BACKFILL FOR ELECTRICAL WORK
 NO ADDITIONAL COMPENSATION WILL BE MADE FOR THESE ITEMS.

12/6/2011 P:\2011\09\09\200\780 CAD & GIS Files\782 Cvt\Sheet\03 Summary of Quantities.dgn

JACOBS ONE NORTH FRANKLIN CHICAGO IL, 60606 312-251-3000	USER NAME =	DESIGNED - CH	REVISED -	KANE COUNTY DIVISION OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE. 360	SECTION 10-00403-00-TL	COUNTY KANE	TOTAL SHEETS 72	SHEET NO. 3
	PLOT SCALE =	DRAWN - MO, DI	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 63648				
PLOT DATE = 12/6/2011	CHECKED - KG	REVISED -					FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT						
	DATE - #DATE	REVISED -											