

SUMMARY OF QUANTITIES

SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	BIKE/PED TRAILS	ROADWAY	ROADWAY	SAFETY	BRIDGE	WATER MAIN ELEC. DISTRIB.
					CMAQ/ITEP/STP 80/20	100% STATE	100% STATE	100% STATE		100% LOCAL
					0028	0001	0004	0021	0008	0043
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	150		30	120			
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	150		30	120			
	20100500	TREE REMOVAL, ACRES	ACRE	3.0		1.5	1.5			
	20101000	TEMPORARY FENCE	FOOT	4,253		2,132	2,121			
	20101100	TREE TRUNK PROTECTION	EACH	100		50	50			
	20200100	EARTH EXCAVATION	CU YD	9,975		5,396	4,579			
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	111			111			
	20700220	POROUS GRANULAR EMBANKMENT	CU YD	102			102			
	20800150	TRENCH BACKFILL	CU YD	5,901			319			5,582
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	19,329		11,790	7,539			
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	40,971		30,270	10,701			
*	25000210	SEEDING, CLASS 2A	ACRE	9.6		9.6				
*	25000320	SEEDING, CLASS 5	ACRE	1.8		1.8				
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	866		866				
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	866		866				
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	866		866				
*	25100115	MULCH, METHOD 2	ACRE	14.5		11	3.5			
*	25100630	EROSION CONTROL BLANKET	SQ YD	26,662		26,662				
	28000305	TEMPORARY DITCH CHECKS	FOOT	143			143			
	28000400	PERIMETER EROSION BARRIER	FOOT	8,752		5,130	3,622			
	28000500	INLET AND PIPE PROTECTION	EACH	13		4	9			
	28000510	INLET FILTERS	EACH	48		36	12			
	28100105	STONE RIPRAP, CLASS A3	SQ YD	180			180			
	28100107	STONE RIPRAP, CLASS A4	SQ YD	1,561		585	27		949	
	28200200	FILTER FABRIC	SQ YD	1,071		459	612			
	35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	5,482	5,482					
	35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	206			206			
	35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	3,817			3,817			
	35600708	HOT-MIX ASPHALT BASE COURSE WIDENING, 8"	SQ YD	1,922			1,922			
	40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,450			2,450			
	40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1,306			1,306			
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	23			23			
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,006			2,006			

PLOT SCALE: 1" = 100' FILE NAME: ... USER NAME: mooleman PLOT DATE: 12/8/2011

FILE NAME =	DESIGNED - MAC	REVISED -
... \pripin-ABC-ht-soq-01.dgn	DRAWN - TMB	REVISED -
USER NAME = mooleman	CHECKED - RMT	REVISED -
PLOT DATE = 12/8/2011	DATE - 10/23/2011	REVISED -



CITY OF ST. CHARLES

SUMMARY OF QUANTITIES			
SCALE: NTS	SHEET NO. 1 OF 9 SHEETS	STA.	TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	04-00092-00-BR	KANE	440	4
CONTRACT NO. 63650			ILLINOIS FED. AID PROJECT	