

SUMMARY OF QUANTITIES

SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	BIKE/PED TRAILS	ROADWAY	ROADWAY	SAFETY	BRIDGE	WATER MAIN ELEC. DISTRIB.
					CMAQ/ITEP/STP 80/20 0028	100% STATE 0001	100% STATE 0004	100% STATE 0021	0008	100% LOCAL 0043
*	XX008631	DRILL EXISTING MANHOLE OR HANDHOLE	EACH	12						12
	Z0019600	DUST CONTROL WATERING	UNIT	100		100				
	Z0022800	FENCE REMOVAL	FOOT	330			330			
	Z0026402	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	2,171			2,171			
	Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 2	EACH	2				2		
	Z0030340	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 2	EACH	2				2		
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	63				63		
*	Z0033056	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1				1		
	Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	1,483			1,483			
	Z0034393	MODULAR EXPANSION JOINT 9"	FOOT	73					73	
	Z0046304	PIPE UNDERDRAINS FOR STRUCTURES, 4"	FOOT	1,117					1,117	
	Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	2,014		2,014				
	Z0076600	TRAINEES	HOUR	1,500						
*	Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1				1		
*	X5610700	WATER MAIN REMOVAL	FOOT	435						435
	Z0077900	WOOD POST AND RAIL FENCE	FOOT	350			350			
	XX008616	HOT-MIX ASPHALT SURFACE COURSE, SPECIAL	SQ YD.	2,897	2,897					
	XX008617	RAIL BASE	FOOT	669				669		
*	XX008618	WATERMAIN, SPECIAL	L SUM	1						1
	XX008619	FURNISHING CABLE STAY SYSTEM	L SUM	1	1					
*	XX008620	BOARDWALK STRUCTURE (SPECIAL)	SQ FT	5,230	5,230					
*	XX008621	PRECAST CONCRETE PYLON TYPE A	EACH	18	18					
*	XX008622	PRECAST CONCRETE PYLON TYPE B	EACH	4	4					
*	XX008623	BRIDGE PYLON FACE LIGHT	EACH	22						22
*	81026464	CONDUIT ENCASED, REINFORCED CONCRETE, 6" DIA., PVC 3 WIDE X 4 HIGH	FOOT	2,057						2,057
*	XX008624	ELECTRICAL MANHOLE, TYPE I, SPECIAL	EACH	4						4
*	XX008625	ELECTRICAL MANHOLE, TYPE II, SPECIAL	EACH	3						3
	XX008626	TEMPORARY BRIDGE	L SUM	1					1	
*	XX008627	^{WATERMAIN} DUCTILE IRON WITHIN 24" CASING PIPE, OPEN CUT, 12"	FOOT	50						50
*	XX008628	^{WATERMAIN} DUCTILE IRON WITHIN 30" CASING PIPE, OPEN CUT, 16"	FOOT	100						100
	XX008629	HAUL ROAD - EAST	L SUM	1		1				
	XX008630	HAUL ROAD - WEST	L SUM	1		1				

• • CONSTRUCTION TYPE CODE 0042

PLOT SCALE: 1:1
 X:\100005\100005\Local\workspace\PlotArea\Drawn\PDF\09 FULL SIZE.plt
 X:\100005\100005\Local\workspace\PlotArea\Title\Title0042.dwg

FILE NAME =	DESIGNED - MAC	REVISED -
... \prpIn-ABC-sht-soq-09.dgn	DRAWN - TMB	REVISED -
USER NAME = mcoleman	CHECKED - RMT	REVISED -
PLOT DATE = 12/8/2011	DATE = 10/23/2011	REVISED -



CITY OF ST. CHARLES

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 9 OF 9 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	04-0092-00-BR	KANE	440	12
CONTRACT NO. 63650			ILLINOIS FED. AID PROJECT	