

ROADWAY SCHEDULE							
ITEM DESCRIPTION	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 (TON)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90 (TON)	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED) (SQ. YD)	CLASS D PATCHES, TYPE II, 14 INCH (SQ. YD)	HOT-MIX ASPHALT SHOULDERS, 8" (SQ. YD)	PROTECTIVE COAT (SQ. YD)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (FOOT)
PAY ITEM NUMBER	40603340	40603595	42000501	44201815	48203029	48301000	60605000
RED GATE ROAD							
BOP TO STA. 98+00.00	128.0	-	-	-	-	-	248.6
STA. 98+00.00 TO STA. 104+00.00	114.4	-	1585	-	-	3170	887.9
STA. 104+00.00 TO STA. 110+00.00	-	-	2004	-	-	4008	854.8
STA. 110+00.00 TO STA. 116+00.00	-	-	-	-	-	-	-
STA. 116+00.00 TO STA. 122+00.00	-	-	236	-	-	472	-
STA. 122+00.00 TO STA. 128+00.00	-	-	1891	-	-	3782	-
STA. 128+00.00 TO EOP	-	-	1916	-	-	3832	762.0
IL-31							
STA. 202+44.00 TO STA. 207+00.00	229.6	-	-	-	407.9	-	-
STA. 207+00.00 TO STA. 213+00.00	490.4	-	-	-	633.9	-	255.8
STA. 213+00.00 TO STA. 218+70.00	245.3	-	-	-	506.9	-	-
IL - 25							
STA. 301+40.00 TO STA. 306+00.00	-	185.9	-	13	-	-	920.0
STA. 306+00.00 TO STA. 312+00.00	-	397.4	-	25	-	-	1040.0
STA. 312+00.00 TO STA. 315+62.00	-	214.6	-	-	-	-	713.0

PLOT SCALE: 1/4" = 100' (1/8" = 50')
 FILE NAME: ...\\ppln-abc-sht-schedule-83.dgn
 USER NAME: mcoleman
 PLOT DATE: 11/18/2011