DRAINAGE STRUCTURE SCHEDULE

STRUCTURE ID	STATION	OFFSET	54213660 FLARED END SECTION - 15"	54247100 GRATING FOR CONCRETE FLARED END SECTION - 15"	60200805 CB TA 4' DIA TY 8	60201340 CB TA 4' DIA W/ T24 F&G	60207605 CB TC TY 8	60218400 MH TY A 4' DIA W/ T1 F&L CL
			EACH	EACH	EACH	EACH	EACH	EACH
IL ROUTE 25								
A-1	303+83.00	19.4				1		
A-15	306+43.00	14.4						1
A-16	304+13.00	33.0			1			
A-2	303+82.00	-19.4				1		
A-3	306+43.00	20.0				1		
A-4	306+43.00	-20.0				1		
A-5	309+42.00	20.0				1		
A-6	309+42.00	14.0						1
A-7	309+42.00	-22.9				1		
B-25	310+24.36	-47.7				1		
B-15	311+32.00	-55.4				1		
A-8	311+47.00	20.0				1		
A-9	311+47.00	34.3			1			
B-16	311+65.00	-18.0						1
G-3	311+66.50	30.8	1	1				
B-18	312+00.00	-29.7				1		
B-17	312+00.00	-16.0						1
G-4	312+01.00	30.8	1	1				
A-11	312+50.00	18.6				1		
A-12	312+50.00	35.0					1	
G-5	312+90.00	32.7	1	1				
B-19	313+00.00	-15.0						1
B-20	313+00.00	-27.5				1		
G-6	313+10.00	30.0	1	1				
A-13	313+50.00	16.4				1		
B-21	313+80.00	-14.0						1
B-22	314+00.00	-30.8				1		
RED GATE ROAD								
E-1	98+67.14	35.5			1			
E-2	98+93.20	35.5					1	
D-18	101+00.02	26.3				1		
D-16	102+00.00	21.0				1		
D-13	103+00.00	-36.5						1
D-14	103+00.00	21.0				1		
D-11	104+00.00	-36.5						1
D-12	104+00.00	21.0				1		
D-24	104+50.00	38.0			1			
D-10	105+00.00	21.0				1		
D-22	105+00.00	39.4			1			
D-9	105+00.00	-27.5						1
D-7	106+00.00	-24.5						1
D-8	106+00.00	20.8				1		
D-3	107+00.00	-26.0						1
D-4	107+00.00	-18.3				1		
D-5	107+00.00	18.2				1		
D-6	107+36.00	17.4				1		
D-0	107+92.00	-42.8	1	1				
D-1	108+00.00	-23.0						1
D-2	108+00.00	-15.7				1		
D-19	108+92.00	-23.0						1
D-20	109+00.00	-15.0				1		
C-14	121+22.00	-15.0				1		
C-15	121+32.00	20.0						1
C-13	121+38.00	13.0				1		
C-5	121+59.63	15.0				1		
C-8	121+59.63	-15.0				1		
C-4	121+74.63	15.0				1		
C-7	121+74.63	-15.0				1		
C-3	121+77.00	22.0						1
C-34	121+80.00	43.0						1
C-10	121+88.00	98.0	1	1				

DRAINAGE STRUCTURE SCHEDULE

STRUCTURE ID	STATION	OFFSET	54213660 FLARED END SECTION - 15"	54247100 GRATING FOR CONCRETE FLARED END SECTION - 15"	60200805 CB TA 4' DIA TY 8	60201340 CB TA 4' DIA W/ T24 F&G	60207605 CB TC TY 8	60218400 MH TY A 4' DIA W/ T1 F&L CL
			EACH	EACH	EACH	EACH	EACH	EACH
C-6	121+89.63	15.0				1		
C-9	121+89.63	-15.0				1		
C-16	122+70.00	15.1				1		
C-17	122+70.00	-15.0				1		
C-18	122+55.00	18.5						1
B-3	127+00.00	46.0						1
B-4	127+00.00	-15.0				1		
B-5	128+00.00	46.0						1
B-6	128+00.00	-14.6				1		
B-7	128+90.00	46.0						1
B-8	128+97.00	42.0				1		
B-9	129+93.00	46.0						1
B-10	130+00.00	42.0				1		
B-11	130+00.00	-14.0				1		
B-12	130+92.00	46.0						1
B-13	131+00.00	42.0				1		
B-14	131+00.00	-14.0				1		
B-23	131+55.00	43.2				1		
IL ROUTE 31								
F-0	206+55.81	29.5	1	1				
F-1	206+55.81	33.9	1	1				
F-2	214+45.00	37.0	1	1				
F-3	213+87.00	39.0	1	1				
F-4	215+40.00	39.0	1	1				
PINELANDS ROAD								
PL-1	801+24.00	35.0	1	1				
PL-2	800+80.00	25.0	1	1				
		TOTAL	13	13	5	43	2	22

DRAINAGE SCHEDULE

STATION	STRUCTURE ID	OFFSET	XX004254 FRAMES AND GRATES TO BE REPLACED
			EACH
303+82.63	EX-CB2	14.0	1
		TOTAL	1

DRAINAGE SCHEDULE

STATION	54248510 CONCRETE COLLAR
	CU YD
215+80.70	1
TOTAL	1

PLOT SCALE:1:1
X:\2020205\100052\Local_Workspace\PlotDRV\Dmn\PDFVB_FULL_SIZE.plt
X:\2020205\100052\Local_Workspace\PlotDRV\TITLEBLOCK.tbl

FILE NAME =	DESIGNED - MAC	REVISED -	
...\prpln-ABC-sht-schedule-04.dgn	DRAWN - TMB	REVISED -	
USER NAME = tblank	CHECKED - RMT	REVISED -	
PLOT DATE = 11/29/2011	DATE - 10/23/2011	REVISED -	

benesch engineers · scientists · planners

ST. CHARLES ILLINOIS

CITY OF ST. CHARLES

SCHEDULE OF QUANTITIES

SCALE: NTS | SHEET NO. 4 OF 16 SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	04-00092-00-BR	KANE	440	16
		CONTRACT NO. 63650		
		ILLINOIS FED. AID PROJECT		