

**TEMPORARY CONCRETE BARRIER SCHEDULE**

LOCATION		OS	STAGE	70400100	70400200
FROM STA	TO STA			TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER
301+75	311+49	10.5 RT	Stage 1	978.28	
311+53	314+48	8.40 LT	Stage 2		295
TOTAL				979	295

**TEMPORARY PAVEMENT MARKING**

STAGE	X7030025	X7030030	X7030040	X7030050	X7030055
	WET REFLECTIVE TEMPORARY TAPE, TYPE III - LETTERS AND SYMBOLS	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH
STAGE 1	73.00	12631.00	895.00	553.00	20.00
STAGE 2	109.00	14026.00	1123.00	331.00	65.00
TOTAL	182	26657	2018	884	85

**TEMPORARY INFORMATION SIGNING SCHEDULE**

SIGN NAME	AREA (EACH)	QUANTITY	QUANTITY (SQ FT)
DRIVEWAY	6.25	10	62.5
TOTAL			63

**IMPACT ATTENUATOR SCHEDULE**

STA	OS	STAGE	Z0030240	Z0030340
			IMPACT ATTENUATORS, TEMPORARY	IMPACT ATTENUATORS, RELOCATE
301+75	10.35 RT	Stage 1	1	
311+49	9.5 RT	Stage 1	1	
311+52	8.51 LT	Stage 2		1
314+49	10 LT	Stage 2		1
TOTAL			2	2

**TEMPORARY ACCESS SCHEDULE**

Location	Station	OFFSET	STAGE	X4021000	X4022000
				TEMPORARY ACCESS (PRIVATE ENTRANCE)	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)
				(EACH)	(EACH)
IL 25	31170	16.3 RT	1	1	
IL 25	31198	15.8 RT	1	1	
IL 25	31297	19.4 RT	1	1	
IL 25	31404	18.7 RT	1	1	
IL31	20917	23.7 RT	1	1	
IL31	21609	25.2 RT	1	1	
IL 25	31637	16.5 LT	2	1	
IL31	21490	18 LT	2	1	
IL 31	21600	30 LT	2	1	
IL 25	309+06	20.7 LT	2		1
TOTAL				9	1

PLOT SCALE: 1/8" = 1'-0" (1/8" = 1'-0")  
 FILE NAME: ...\\pripin-abc-sht-schedule-26.dgn  
 USER NAME: mcoleman  
 PLOT DATE: 11/10/2011

DESIGNED - MAC	REVISED -
DRAWN - TMB	REVISED -
CHECKED - RMT	REVISED -
DATE - 10/23/2011	REVISED -



**CITY OF ST. CHARLES**

**SCHEDULE OF QUANTITIES**

SCALE: NTS SHEET NO. 6 OF 16 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	04-00092-00-BR	KANE	440	18
CONTRACT NO. 63650			ILLINOIS FED. AID PROJECT	