

**EARTHWORK SCHEDULE**

(1) LOCATION	(2) EARTH EXCAVATION	(3) UNSUITABLE OR UNSTABLE MATERIAL	(4) EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SCHRINKAGE	(5) EMBANKMENT	(6) EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	(7) TOPSOIL EXCAVATION	(8) TOPSOIL PLACE
<b>RED GATE ROAD</b>							
STA. 96+00.00 TO STA. 109+10.81	2,593	0	2,204	2,156	48	0	379
STA. 121+00.00 TO STA. 124+51.12	0	0	0	397	-397	0	98
STA. 126+16.12 TO STA. 132+00.00	0	0	0	585	-585	0	147
<b>IL 31</b>							
STA. 201+50.00 TO STA. 209+50.00	1,113	0	946	551	395	929	373
STA. 210+50.00 TO STA. 218+50.00	995	0	846	432	414	652	238
<b>IL 25</b>							
STA. 301+50.00 TO STA. 310+00.00	2,096	0	1,782	287	1,495	668	354
STA. 311+50.00 TO STA. 315+00.00	359	90	306	621	-315	345	203
<b>PINELANDS</b>							
STA. 800+00.00 TO STA. 801+00.00	15	0	13	159	-146	53	20
<b>TOTAL</b>	<b>7,172</b>	<b>90</b>	<b>6,097</b>	<b>5,189</b>	<b>908</b>	<b>2,647</b>	<b>1,812</b>

PLOT SCALE: 1/4" = 100' (1/8" = 50')  
 FILE NAME: ...\\prpln-abc-sht-schedule-07.dgn  
 USER NAME: mooleman  
 PLOT DATE: 11/10/2011

FILE NAME =	DESIGNED - MAC	REVISED -
...\\prpln-abc-sht-schedule-07.dgn	DRAWN - TMB	REVISED -
USER NAME = mooleman	CHECKED - RMT	REVISED -
PLOT DATE = 11/10/2011	DATE - 10/23/2011	REVISED -



**CITY OF ST. CHARLES**

SCHEDULE OF QUANTITIES			
SCALE: NTS	SHEET NO. 7 OF 16 SHEETS	STA.	TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	04-00092-00-BR	KANE	440	19
CONTRACT NO. 63650			ILLINOIS FED. AID PROJECT	