

EARTH EXCAVATION ---- RED GATE ROAD

STATION	CUT END AREA (SF)	FILL END AREA (SF)	CUT AVERAGE END AREA (SF)	FILL AVERAGE END AREA (SF)	LENGTH (FT)	EXCAVATION (CUT) VOLUME (CU YD)	EMBANKMENT (FILL) VOLUME (CU YD)	CUMULATIVE EXCAVATION VOLUME (CU YD)	CUMULATIVE EMBANKMENT VOLUME (CU YD)
121+00.00	0.00	0.00							
121+22.24	0.00	40.19	0.00	20.10	22.24	0.00	16.55	2592.77	2172.61
121+50.00	0.00	29.23	0.00	34.71	27.76	0.00	35.69	2592.77	2208.29
122+00.00	0.00	29.23	0.00	29.23	50.00	0.00	54.13	2592.77	2262.42
122+50.00	0.00	25.75	0.00	27.49	50.00	0.00	50.91	2592.77	2313.33
123+00.00	0.00	29.22	0.00	27.49	50.00	0.00	50.90	2592.77	2364.23
123+50.00	0.00	29.22	0.00	29.22	50.00	0.00	54.11	2592.77	2418.34
124+00.00	0.00	29.22	0.00	29.22	50.00	0.00	54.11	2592.77	2472.45
124+50.00	0.00	55.40	0.00	42.31	50.00	0.00	78.35	2592.77	2550.80
124+51.12	0.00	56.56	0.00	55.98	1.12	0.00	2.32	2592.77	2553.12
BRIDGE OMISSION									
126+16.12	0.36	29.53							
126+50.00	0.00	26.87	0.18	28.20	33.88	0.23	35.39	2592.99	2588.51
127+00.00	0.00	26.86	0.00	26.87	50.00	0.00	49.75	2592.99	2638.26
127+50.00	0.00	27.58	0.00	27.22	50.00	0.00	50.41	2592.99	2688.67
128+00.00	0.00	32.13	0.00	29.86	50.00	0.00	55.29	2592.99	2743.95
128+50.00	0.00	27.92	0.00	30.03	50.00	0.00	55.60	2592.99	2799.56
129+00.00	0.00	27.61	0.00	27.77	50.00	0.00	51.42	2592.99	2850.97
129+50.00	0.00	28.89	0.00	28.25	50.00	0.00	52.31	2592.99	2903.29
130+00.00	0.00	29.69	0.00	29.29	50.00	0.00	54.24	2592.99	2957.53
130+50.00	0.00	29.69	0.00	29.69	50.00	0.00	54.98	2592.99	3012.51
131+00.00	0.00	29.69	0.00	29.69	50.00	0.00	54.98	2592.99	3067.49
131+50.00	0.00	23.46	0.00	26.58	50.00	0.00	49.21	2592.99	3116.70
132+00.00			0.00	11.73	50.00	0.00	21.72	2592.99	3138.43

PLOT SCALE: 1/4" = 10'-0" (PLOT FULL SIZE) FILE NAME: ... \p\in-abc-sht-schedule-29.dgn USER NAME: mbolemo PLOT DATE: 11/12/2011

FILE NAME =	DESIGNED - MAC	REVISED -
... \p\in-abc-sht-schedule-29.dgn	DRAWN - TMB	REVISED -
USER NAME = mbolemo	CHECKED - RMT	REVISED -
PLOT DATE = 11/12/2011	DATE - 10/23/2011	REVISED -



CITY OF ST. CHARLES

SCHEDULE OF QUANTITIES

SCALE: NTS SHEET NO. 9 OF 16 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	04-00092-00-BR	KANE	440	21
CONTRACT NO. 63650			ILLINOIS FED. AID PROJECT	