SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITIES
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	411
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	2709
81100605	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL	FOOT	1,207
81200210	CONDUIT EMBEDDED IN STRUCTURE, 1" DIA., PVC	FOOT	322
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	240
81300420	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 10" X 8" X 6"	EACH	19
81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	5,587
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	11,857
81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	129
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	21
82500350	LIGHTING CONTROLLER, BASE MOUNTED, 240 VOLT, 100 AMP	EACH	2
83050825	LIGHT POLE, ALUMINUM, 47.5 FT M.H., 15 FT DAVIT ARM	EACH	21
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	147
X0325923	CONDUIT, FLEXIBLE NON-METALLIC, WEATHERPROOF, 1" DIAMETER	FOOT	42
X0326962	TRANSFORMER PLATFORM	SQ YD	1.5
	BRIDGE PYLON FACE LIGHT	EACH	22

SHEET L-2

PLOT SCALE: 1:1
X:\10000S\10092\Local_Workspace\PlotDRV\Omn:PDFV8 FULL SIZE.plt
X:\10000S\10092\Local_Workspace\PlotDRV\TITLEBLOCK.tbl

FILE NAME =	DESIGNED - BC	REVISED -	
...\prpln-ABC-sht-ADV-lightsoq.dgn	DRAWN - BC	REVISED -	
USER NAME = mooleman	CHECKED - MPM	REVISED -	
PLOT DATE = 12/8/2011	DATE 10/23/2011	REVISED -	

benesch engineers · scientists · planners

ST. CHARLES SINCE 1834

CITY OF ST. CHARLES

LIGHTING
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 2 OF 10 SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	04-00092-00-BR	KANE	440	210
		CONTRACT NO. 63650		
		ILLINOIS FED. AID PROJECT		