

SUMMARY OF QUANTITIES

	CODE	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
					RECONSTRUCT 0004	RECONSTRUCT 0004
					75% FEDERAL 25% LOCAL	100% LOCAL
~	60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	49	49	0
~	60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5	0
~	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	48	48	0
	60500040	REMOVING MANHOLES	EACH	5	5	0
	60500050	REMOVING CATCH BASINS	EACH	35	35	0
	60500060	REMOVING INLETS	EACH	12	12	0
	60500105	FILLING MANHOLES	EACH	1	1	0
~	60604100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (MODIFIED)	FOOT	11,500	7,810	3,690
~	60604700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18 (MODIFIED)	FOOT	190	95	95
~	61141000	STORM SEWERS (SPECIAL), 27"	FOOT	15	15	0
*	66900200	NON-SPECIAL WASTE DISPOSAL	CUYD	200	200	0
*	66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1	0
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1	0
	67100100	MOBILIZATION	L SUM	1	1	0
	70106800	CHANGEABLE MESSAGE SIGN	CAL-MO	1	1	0
	72000100	SIGN PANEL - TYPE 1	SQFT	360	360	0
	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	680	680	0
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQFT	65	65	0
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7,200	7,200	0
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,655	2,655	0
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	590	590	0
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	465	465	0
*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	260	260	0
~	Z0001050	AGGREGATE SUBGRADE 12"	SQYD	5,500	5,500	0
~	Z0019600	DUST CONTROL WATERING	UNIT	100	100	0
~	Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CUYD	2,380	1,650	730
~	Z0076600	TRAINEES	HOURL	500	500	0
*	B2005524	TREE, PYRUS CALLERYANA ARISTOCRAT (ARISTOCRAT CALLERY PEAR), 3" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	3	3	0
~	K1003679	MULCH	CUYD	70	70	0
~	X0324636	WATER VALVE BOXES TO BE ABANDONED	EACH	3	3	0
~	X0325207	TELEVISION INSPECTION OF SEWER	FOOT	6,015	6,015	0
~	Z0062450	TEMPORARY PAVEMENT (VARIABLE DEPTH)	TON	30	30	0
~	X0539800	TREE GRATES	EACH	3	3	0
~	X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQYD	700	125	575
~	X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQYD	10,400	9,800	600
~	X5620096	WATER SERVICE LINE 1", (BORED)	EACH	20	0	20
~	X5620128	ADJUSTING WATER SERVICE LINES	EACH	65	65	0
~	X6026624	VALVE BOXES TO BE ADJUSTED (SPECIAL)	EACH	20	20	0
~	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	0
~	XX000541	EXPLORATORY EXCAVATION	CUYD	350	350	0
~	XX000679	CUT AND CAP EXISTING WATER MAIN	EACH	3	0	3
~	XX000717	STORM SEWER CONNECTION, SPECIAL	EACH	1	1	0
~	XX001464	SANITARY SEWERS, PVC, 6"	FOOT	995	995	0
~	XX003059	DECORATIVE BRICK SIDEWALK	SQFT	4,425	4,425	0
~	XX005195	COMBINED SEWER MANHOLE, 4'-DIAMETER TYPE 1 FRAME, CLOSED LID	EACH	6	6	0
~	XX005636	PIPE UNDERDRAINS, PERFORATED POLYVINYL CHLORIDE PIPE, 6"	FOOT	408	408	0
~	XX006281	STORM SEWERS, DUCTILE IRON, TYPE 1 10"	FOOT	69	69	0
~	XX006282	STORM SEWERS, DUCTILE IRON, TYPE 1 12"	FOOT	110	110	0
~	XX006448	10" PVC COMBINED SEWER PIPE REPLACEMENT	FOOT	7	7	0
~	XX006449	12" PVC COMBINED SEWER PIPE REPLACEMENT	FOOT	131	131	0
~	XX006450	15" PVC COMBINED SEWER PIPE REPLACEMENT	FOOT	272	272	0
~	XX006452	15"x 6" PVC SEWER SERVICE CONNECTIONS	EACH	3	3	0
~	XX007001	ROOT BARRIER	EACH	3	3	0
~	XX007558	GATE VALVE 6" WITH VAULT, 4' DIAMETER	EACH	3	0	3
~	XX008599	PVC COMBINED SEWER PIPE REPLACEMENT 18"	FOOT	15	15	0
~	XX104100	CONNECTION TO EXISTING MANHOLE	EACH	7	7	0
~	XX008101	BIOSWALE	L SUM	1	1	0
~	XX008101	TRENCH DEWATERING	EACH	6	6	0

* DENOTES SPECIALTY ITEM
 ~ DENOTES THAT A SPECIAL PROVISION HAS BEEN PROVIDED

△ 0042

Drawing file: W:\Projects\12509232 - Grand Blvd. Design Engineer\Sum_Quantities.dwg Nov. 22, 2011 - 10:37am

HANCOCK ENGINEERING
 Civil Engineers
 Municipal Consultants
 Established 1911

USER NAME -	DESIGNED - WOP, JG	REVISED -
PLOT SCALE -	DRAWN - MK, DMM	REVISED -
PLOT DATE -	CHECKED - WOP, JG	REVISED -
	DATE - 10-24-11	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NOT TO SCALE SHEET NO. 1 OF 2 SHEETS STA. - TO STA. -

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAU 1694	07-00122-01-PV	COOK	86	5
FIELD BOOK NO. -AERIALS/LL		CONTRACT NO. 63651		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003(875)				