

SUMMARY OF QUANTITIES				0005 ROADWAY 70% STP 30% LA
CODE NO	PAY ITEM	UNIT	QUANTITY	
20200100	EARTH EXCAVATION	CU YD	625	625
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,334	1,334
20400800	FURNISHED EXCAVATION	CU YD	256	256
20800150	TRENCH BACKFILL	CU YD	12	12
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	6,173	6,173
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	77	77
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	77	77
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	77	77
25200110	SODDING, SALT TOLERANT	SQ YD	6,173	6,173
25200200	SUPPLEMENTAL WATERING	UNIT	19	19
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	128	128
28000400	PERIMETER EROSION BARRIER	FOOT	1,775	1,775
28000500	INLET AND PIPE PROTECTION	EACH	9	9
28000510	INLET FILTERS	EACH	17	17
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	2,607	2,607
35800100	PREPARATION OF BASE	SQ YD	22,444	22,444
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,663	4,663
40600300	AGGREGATE (PRIME COAT)	TON	94	94
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	30	30
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,230	1,230
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	229	229
40600990	TEMPORARY RAMP	SQ YD	229	229
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	584	584
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2,708	2,708
42001300	PROTECTIVE COAT	SQ YD	279	279
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	149	149
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	267	267
42400800	DETECTABLE WARNINGS	SQ FT	73	73
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	22,215	22,215
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	797	797
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	396	396
44000600	SIDEWALK REMOVAL	SQ FT	340	340
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	834	834
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	834	834
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	834	834
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	834	834
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	306	306
50105220	PIPE CULVERT REMOVAL	FOOT	136	136
54215547	METAL END SECTIONS 12"	EACH	2	2
54215550	METAL END SECTIONS 15"	EACH	5	5
54215553	METAL END SECTIONS 18"	EACH	2	2
54215559	METAL END SECTIONS 24"	EACH	2	2

SUMMARY OF QUANTITIES				0005 ROADWAY 70% STP 30% LA
CODE NO	PAY ITEM	UNIT	QUANTITY	
542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	14	14
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	11	11
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	22	22
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	10	10
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3
60404805	FRAMES AND GRATES, TYPE 11V	EACH	2	2
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	396	396
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	3,257	3,257
* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	19,405	19,405
* 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	137	137
* 70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	675	675
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	32,341	32,341
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	79	79
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	152	152
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	228	228
Z0004522	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 6"	SQ YD	560	560
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	4	4
Z0023202	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	34	34
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	402	402
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	56	56
** Z0076600	TRAINEES	hour	500	500

* SPECIALTY ITEM

** TRAINEES CONSTRUCTION
TYPE CODE = 0042

FILE NAME = g:\CH09\0008\Road\Sheets\G-1029-500.SHT	USER NAME = USER	DESIGNED - CEC	REVISED -
		DRAWN - JKM	REVISED -
	PLOT SCALE = 69.3996 Ft / INL	CHECKED - DWB	REVISED -
	PLOT DATE = 11/1/2011	DATE - 10/24/2011	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAIR OAKS ROAD
SUMMARY OF QUANTITIES

NOT TO SCALE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.U. RTE. 2542	SECTION 11-00057-00-RS	COUNTY DUPAGE	TOTAL SHEETS 32	SHEET NO. 3
CONTRACT NO. 63653				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				