

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY LAPP 0005
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	110	110
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	238	238
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3	3
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3	3
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3	3
25200110	SODDING, SALT TOLERANT	SQ YD	238	238
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	13	13
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	2	2
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	2	2
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	50	50
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	12,914	12,914
40600300	AGGREGATE (PRIME COAT)	TON	258	258
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	15	15
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2,712	2,712
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	913	913
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	215	215
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1	1
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	6,328	6,328
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	2	2

\* = SPECIALTY ITEM

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY LAPP 0005
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	2	2
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2,039	2,039
42400800	DETECTABLE WARNINGS	SQ FT	442	442
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	63,657	63,657
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	2	2
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	5.4	5.4
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	256	256
44000600	SIDEWALK REMOVAL	SQ FT	2,000	2,000
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SQ YD	640	640
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	160	160
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	160	160
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	160	160
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	160	160
48101200	AGGREGATE SHOULDERS, TYPE B	TON	30	30
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	233	233
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	16	16
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	7	7
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1

(1) = INCLUDES REMOVAL

FILE NAME - D:\naperv\11e\_253678E4\_Book1\APP\Roadway\Drawings\Quant\Summary Sheets\S00.dgn



USER NAME = #USER*	DESIGNED - EVI	REVISED -
PLOT SCALE = 50.0000' / 1" IN.	DRAWN - KJB	REVISED -
PLOT DATE = 11/29/2011 10:18:43 AM	CHECKED - DAK	REVISED -
	DATE - 10/24/2011	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

NTS SHEET NO. 1 OF 2 SHEETS STA. — TO STA. —

F.A.U. RTE. 0082	SECTION 11-00149-00-RS	COUNTY WILL	TOTAL SHEETS 30	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS			CONTRACT NO. 63659	