

SUMMARY OF QUANTITIES			80% FEDERAL, 20% STATE			
SP	ITEM NUMBER	DESCRIPTION	UNIT	TOTAL	ROADWAY 0004	BRIDGE 0011
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	39	39	
	20101100	TREE TRUNK PROTECTION	EACH	5	5	
	20200100	EARTH EXCAVATION	CU YD	30	30	
	20300100	CHANNEL EXCAVATION	CU YD	90	90	
	21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	60.0	60.0	
*	25000110	SEEDING, CLASS 1A	ACRE	0.07	0.07	
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	10	
*	25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	10	10	
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	10	
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20	20	
	28000400	PERIMETER EROSION BARRIER	FOOT	381	381	
	28100107	STONE RIP RAP, CLASS A4	SQ YD	350		350
	28200200	FILTER FABRIC	SQ YD	350		350
	31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	63.0	63.0	
	40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	283	283	
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	21	21	
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19, N50	TON	62	62	
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	71	71	
	42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	35	35	
	44000100	PAVEMENT REMOVAL	SQ YD	201	201	
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	170	170	
	48101200	AGGREGATE SHOULDERS, TYPE B	TONS	46	46	
	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
	50200100	STRUCTURE EXCAVATION	CU YD	187		187
	50300225	CONCRETE STRUCTURES	CU YD	49.8	12.8	37.0
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	48.1		48.1
	50300280	CONCRETE ENCASEMENT	CU YD	3.6		3.6
	50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	1642		1642
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	19760		19760
*	50901050	STEEL RAILING, TYPE SM	FOOT	130		130

SUMMARY OF QUANTITIES			80% FEDERAL, 20% STATE			
SP	ITEM NUMBER	DESCRIPTION	UNIT	TOTAL	ROADWAY 0004	BRIDGE 0011
	51201610	FURNISHING STEEL PILES HP 12X63	FOOT	292		292
	51202305	DRIVING PILES	FOOT	292		292
	51203610	TEST PILE STEEL HP 12X63	EACH	2		2
	51204650	PILE SHOES	EACH	10		10
	51500100	NAME PLATES	EACH	1		1
	58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	443		443
	58700300	CONCRETE SEALER	SQ FT	432		432
	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	66		66
	60300350	MANHOLE FRAMES TO BE ADJUSTED	EACH	1	1	
*	63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
*	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8	
	67100100	MOBILIZATION	L SUM	1	1	
	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
*	78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	820	560	260
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4	
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
	X0326806	WASHOUT BASIN	L SUM	1	1	
	X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	99	99	
*	X2511630	EROSION CONTROL BLANKET (SPECIAL)	SQ YD	453	453	
	X5810100	WATERPROOFING MEMBRANE SYSTEM (SPECIAL)	SQ YD	183		183
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
	Z0046304	PIPE UNDERDRAINS FOR STRUCTURES, 4"	FOOT	108		108
*	A2000170	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE MAPLE), 8' HEIGHT CLUMP FORM, BALLED AND BURLAPPED	EACH	2	2	
*	K1005421	SEEDING, SPECIAL	ACRE	0.03	0.03	

\* SPECIALTY ITEMS



DESIGNED -- JJT	REVISED --
DRAWN -- ASK	REVISED --
CHECKED -- JJT	REVISED --
DATE -- 10/7/2011	REVISED --

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
AUSTIN AVE OVER INDIAN CREEK

SCALE: NONE SHEET NO. 1 OF 1 STA. 11+83.56 TO STA. 13+88.72

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	03-01130-00-BR	KANE	33	3
D-91-352-04			CONTRACT NO. 63660	
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				