

- SPECIALITY ITEM
- NON-PARTICIPATING ITEM
- 100% WINNEBAGO COUNTY COST

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODES								
				URBAN I-90 CONSTRUCTION 90% FEDERAL 10% STATE 0003	BRIDGE SN. 101-0193 90% FEDERAL 10% STATE 0010	BRIDGE SN. 101-0194 90% FEDERAL 10% STATE 0010	BOX CULVERT SN. 101-1095 90% FEDERAL 10% STATE 0040	ROCKTON • WB I-90 SIGNALS 90% FEDERAL 3.34% STATE 6.66% WINNEBAGO COUNTY 0021	ROCKTON • EB I-90 SIGNALS 90% FEDERAL 3.34% ISTHA 6.66% WINNEBAGO COUNTY 0021	ISTHA SIGNS 100% ISTHA 0021	WISDOT DMS SIGN 100% WISCONSIN DOT 0021	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	113	113								
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	219	219								
20100500	TREE REMOVAL, ACRES	ACRE	0.25	0.25								
20200100	EARTH EXCAVATION	CU YD	134615	134615								
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	10407	10407								
20300100	CHANNEL EXCAVATION	CU YD	2252	2252								
20400800	FURNISHED EXCAVATION	CU YD	5943	5943								
20700110	POROUS GRANULAR EMBANKMENT	TON	183	183								
20800150	TRENCH BACKFILL	CU YD	1062	1062								
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	12823	12823								
25000210	SEEDING, CLASS 2A	ACRE	31	31								
25000310	SEEDING, CLASS 4	ACRE	4	4								
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2579	2579								
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2579	2579								
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2579	2579								
•• 25000750	MOWING	ACRE	44	44								
25100115	MULCH, METHOD 2	ACRE	27.5	27.5								
25100630	EROSION CONTROL BLANKET	SO YD	30841	30841								
25100900	TURF REINFORCEMENT MAT	SO YD	2534	2534								
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	25600	25600								
28000305	TEMPORARY DITCH CHECKS	FOOT	1967	1967								
28000400	PERIMETER EROSION BARRIER	FOOT	35202	35202								
28000500	INLET AND PIPE PROTECTION	EACH	72	72								
28001000	AGGREGATE (EROSION CONTROL)	TON	67	67								
28100105	STONE RIPRAP, CLASS A3	SO YD	40	40								
28100109	STONE RIPRAP, CLASS A5	SO YD	2879	1129	926	824						
28200200	FILTER FABRIC	SO YD	3072	1169	1012	891						
31100100	SUBBASE GRANULAR MATERIAL, TYPE A	TON	403	403								
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SO YD	175958	175958								
31100935	SUBBASE GRANULAR MATERIAL, TYPE A 18"	SO YD	13862	13862								
31100950	SUBBASE GRANULAR MATERIAL, TYPE A 21"	SO YD	2543	2543								
31100965	SUBBASE GRANULAR MATERIAL, TYPE A 24"	SO YD	11281	11281								
31200100	STABILIZED SUBBASE 4"	SO YD	11218	11218								
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SO YD	192491	192491								
35101400	AGGREGATE BASE COURSE, TYPE B	TON	1824	1824								
35600700	HOT-MIX ASPHALT BASE COURSE WIDENING, 6"	SO YD	613	613								
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	13	13								
40600300	AGGREGATE (PRIME COAT)	TON	6	6								
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	614	614								
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	134	134								
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	241	241								
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	130	130								
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	733	733								
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	253	253								



USER NAME = .USERNAME.	DESIGNED -	REVISED -
FILE NAME = #FILE#	DRAWN - KRL	REVISED -
PLOT SCALE = 50.0000' / 1" IN.	CHECKED - PDS	REVISED -
PLOT DATE = 11/15/2011	DATE - 10-21-2011	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	(X2-1) R	WINNEBAGO	510	7
CONTRACT NO. 64C29				
ILLINOIS FED. AID PROJECT				