

- SPECIALITY ITEM
- NON-PARTICIPATING ITEM
- 100% WINNEBAGO COUNTY COST

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODES									
				I-90 CONSTRUCTION 90% FEDERAL 10% STATE 0003	BRIDGE SN. 101-0193 90% FEDERAL 10% STATE 0010	BRIDGE SN. 101-0194 90% FEDERAL 10% STATE 0010	BOX CULVERT SN. 101-1095 90% FEDERAL 10% STATE 0040	ROCKTON @ WB I-90 SIGNALS 90% FEDERAL 3.34% STATE 6.66% WINNEBAGO COUNTY 0021	ROCKTON @ EB I-90 SIGNALS 90% FEDERAL 3.34% ISTHA 6.66% WINNEBAGO COUNTY 0021	ISTHA SIGNS 100% ISTHA 0021	WISDOT DMS SIGN 100% WISCONSIN DOT 0021		
52100520	ANCHOR BOLTS, 1"	EACH	136										
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2				2						
54010804	PRECAST CONCRETE BOX CULVERTS 8' X 4'	FOOT	352				352						
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FOOT	47	47									
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	145	145									
542A1093	PIPE CULVERTS, CLASS A, TYPE 2 48"	FOOT	91	91									
542A5491	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	108	108									
5421A018	PIPE CULVERTS, CLASS A, TYPE 1 18" (TEMPORARY)	FOOT	599	599									
5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT	25	25									
5422A018	PIPE CULVERTS, CLASS A, TYPE 2 18" (TEMPORARY)	FOOT	193	193									
5422A024	PIPE CULVERTS, CLASS A, TYPE 2 24" (TEMPORARY)	FOOT	88	88									
5422A036	PIPE CULVERTS, CLASS A, TYPE 2 36" (TEMPORARY)	FOOT	84	84									
5423A018	PIPE CULVERTS, CLASS A, TYPE 3 18" (TEMPORARY)	FOOT	126	126									
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	32	32									
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	4	4									
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	2	2									
54214503	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	8	8									
54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	1	1									
54214941	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ARCH, EQUIVALENT ROUND-SIZE 36"	EACH	2	2									
54215424	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 24"	EACH	2	2									
54215547	METAL END SECTIONS 12"	EACH	2	2									
54248160	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 36"	EACH	2	2									
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	400	400									
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	606	606									
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	265	265									
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	243	243									
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	516	516									
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	2616	2616									
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	823	823									
550A0680	STORM SEWERS, CLASS A, TYPE 3 18"	FOOT	100	100									
550A4000	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	792	792									
550A4100	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	308	308									
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	225			120	105						
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	71	71									
60100945	PIPE DRAINS 12"	FOOT	71	71									
60107600	PIPE UNDERDRAINS 4"	FOOT	38688	38688									
60107700	PIPE UNDERDRAINS 6"	FOOT	9602	9602									
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	175	175									
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2									
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1									
60270050	DRAINAGE STRUCTURES, TYPE 4 WITH TWO TYPE 20 FRAME AND GRATES	EACH	47	47									
60270055	DRAINAGE STRUCTURES, TYPE 5 WITH TWO TYPE 22 FRAME AND GRATES	EACH	3	3									
60300105	FRAME AND GRATE TO BE ADJUSTED	EACH	3	3									
60500040	REMOVING MANHOLES	EACH	2	2									



USER NAME = .USERNAME.	DESIGNED -	REVISED -
FILE NAME = #FILE#	DRAWN - KRL	REVISED -
PLOT SCALE = 50.0000' / IN.	CHECKED - PDS	REVISED -
PLOT DATE = 11/15/2011	DATE - 10-21-2011	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	(X2-1) R	WINNEBAGO	510	9
CONTRACT NO. 64C29				
ILLINOIS FED. AID PROJECT				