

CONCRETE REMOVAL SCHEDULE

				40600985	44000500	44003100	44004250	Z0004552	X4400100	X4402805	X4402805
				PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	COMBINATION CURB AND GUTTER REMOVAL	MEDIAN REMOVAL	PAVED SHOULDER REMOVAL	APPROACH SLAB REMOVAL	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	ISLAND PAVEMENT REMOVAL	ISLAND REMOVAL
STATION	OFF	STATION	OFF	SO YD	FOOT	SO FT	SO YD	SO YD	SO YD	SO YD	SO FT
I-90 EXIT RAMP TO VISITOR CENTER											
7+99.40	LT	11+00.00	LT				134				
7+99.40	RT	11+00.00	RT				201				
11+00.00				107							
I-90 ENTRANCE RAMP FROM VISITOR CENTER											
37+00.00	LT	37+31.08	LT				14				
37+00.00	RT	37+31.08	RT				21				
37+00.00				107							
VISITOR CENTER PARKING LOTS				27					1579		
I-90 MAINLINE AND IL-75 RAMP A											
989+92.41	LT	6+11.84	LT				1746				
I-90 MAINLINE AND IL-75 RAMP D											
989+59.28	RT	4+15.77	RT				1191				
I-90											
985+59.89	LT	0+00.00	LT				664				
983+26.42	RT	989+25.12	RT				222				
990+90.67	LT	0+00.00	LT				274				
IL-75 RAMP B											
20001+85.48	RT	20006+45.15	RT				296				
20005+53.56	LT	20006+45.29	LT				61				
IL-75 RAMP C											
30005+95.82	LT	30008+37.93	LT				93				
RAMPS											
300+24.24		309+71.28	RT				818				
300+24.24		309+71.28	LT				794				
406+78.62		420+51.91	RT				1147				
406+78.62		420+33.41	LT				726				
30004+90.63		30005+70.00	RT				54				
30004+90.63		30005+70.00	LT				36				
20006+45.20		20010+54.20	RT				284				
20006+45.20		20010+54.20	LT				164				
ROCKTON RD											
NW RAMP ISLAND											
4998+96.05		5001+88.51									650
4999+01.96		5001+83.52				2544					
4999+01.96		5001+83.52		564							
WB Rockton Rd Exit					27					4	
BRIDGE APPROACH											
NE								148			
SE								148			
NW								181			
SW								172			
TOTAL				241	591	2544	8940	649	1579	4	650



USER NAME = .USERNAME.
 FILE NAME = *FILE*
 PLOT SCALE = 50.0000' / IN.
 PLOT DATE = 10/20/2011

DESIGNED -
 DRAWN - KRL
 CHECKED - POS
 DATE - 10-21-2011

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N/A SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	(X2-1) R	WINNEBAGO	510	47
CONTRACT NO. 64C29			ILLINOIS FED. AID PROJECT	