

TEMPORARY PAVEMENT MARKINGS / REMOVAL SCHEDULE

				70300220	70300250	78001110	78001130	78001140	78001150	70301000	78300100	JT783005
				TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 8"	PAINT PAVEMENT MARKING - LINE 4"	PAINT PAVEMENT MARKING - LINE 6"	PAINT PAVEMENT MARKING - LINE 8"	PAINT PAVEMENT MARKING - LINE 12"	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL	WATERBLAST PAVEMENT MARKING REMOVAL WITH VACUUM RECOVERY
STATION	OFF	STATION	OFF	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SO FT	SO FT	SO FT
0+00.00	WB	0+92.10	WB					92				
0+00.00	WB	0+92.80	WB					93				
0+00.00	EB	5+43.10	EB					543		80		
0+00.00	EB	134+20.40	EB			26841						
0+00.00	EB - CTR	134+20.40	EB - CTR								1680	
0+00.00	EB - SHLD	134+20.40	EB - SHLD								8946	
0+00.00	WB	134+20.40	WB			13420	6720					
0+00.00	EB	134+20.41	EB				3360					
0+92.80	WB	31+06.80	WB			3014						
1+05.70	EB	5+43.10	EB					437	462			
2+07.50	EB	7+99.40	EB					592				
26+16.98	EB	31+01.70	EB						200			
26+25.00	EB	48+60.90	EB					2236				
26+31.70	EB	31+01.70	EB					470				
31+06.79	WB	51+36.10	WB					2029				
31+06.80	WB	35+75.80	WB						572			
31+35.00	WB	35+75.80	WB									
36+29.50	WB	121+64.90	WB			8535		441				
37+31.10	EB	72+08.40	EB					664				
43+55.40	EB	48+60.92	EB						552			
43+55.40	EB	48+61.50	EB					506				
51+36.10	WB	54+86.10	WB					90				
65+28.00	EB	72+08.40	EB					680				
65+28.01	EB	72+08.40	EB						310			
65+43.50	EB	72+08.40	EB					665				
72+08.00	EB	79+25.40	EB					180				
121+64.90	WB	128+82.00	WB					180				
121+64.90	WB	309+71.30	WB					1212				
124+02.90	EB	126+71.30	EB					70				
126+71.30	EB	130+62.60	EB					391				
126+71.30	EB	130+62.80	EB					392	272			
128+82.00	WB	133+78.60	WB					497				
128+82.00	WB	133+91.90	WB					510				
128+82.10	WB	133+91.90	WB						210			
133+91.90	WB	134+20.40	WB			48						
400+18.70	EB	406+78.60	EB					660				
981+13.84	WB	134+20.40	WB								18566	
981+13.84	EB	991+11.70	EB									
981+13.84	EB	1000+00.00	EB			3772	250	480				
981+13.84	EB - IN	1000+00.00	EB - IN									
981+13.84	EB - OUT	1000+00.00	EB - OUT								629	
981+13.84	EB - SKIP	1000+00.00	EB - SKIP								629	
982+79.90	EB - SKIP	991+11.70	EB - SKIP								240	
983+60.50	WB	992+93.50	WB								105	
983+60.50	WB	996+38.70	WB			1278	240					
983+60.50	WB	1000+00.00	WB			1640	410					
983+60.55	WB - OUT	996+38.70	WB - OUT								426	
983+60.55	WB - IN	1000+00.00	WB - IN								546	
983+60.55	WB - SKIP	1000+00.00	WB - SKIP								205	
991+11.70	EB	1000+00.00	EB						888			
991+11.70	EB - LANE	1000+00.00	EB - LANE								592	
992+93.50	WB	996+39.00	WB					346				
992+93.50	WB - LANE	996+39.00	WB - LANE								230	
992+93.50	WB - SKIP	1000+00.00	WB - SKIP								90	
996+38.70	WB	1000+00.00	WB					1084				
996+38.70	WB - LANE	1000+00.00	WB - LANE								723	
20010+54.20	EB	20015+25.60	EB					471				
30004+90.60	WB	30000+00.00	WB					491				
PRESTAGE A												
1+00.00		9+00.00		800						267		
9+00.00		23+00.00		1400						467		
23+00.00		37+00.00		1400						467		
37+00.00		65+00.00		2800						933		
65+00.00		93+00.00		2800						933		
93+00.00		121+00.00		2800						933		
121+00.00		135+00.00		1400						467		
135+00.00		144+00.00		900						300		
144+00.00		151+48.00		748						249		
PRESTAGE C												
985+28.00		9+00.00		5280						1759		
STAGE 1A												
9+00.00		23+00.00		6548						2183		
23+00.00		37+00.00		11969	238					3989		
37+00.00		51+00.00		7671	388					2816		
51+00.00		65+00.00		6534						2178		
65+00.00		79+00.00		7901						2634		
79+00.00		93+00.00		6534						2178		
93+00.00		107+00.00		6534						2178		
107+00.00		121+00.00		8324	315					2985		
121+00.00		135+00.00		13505	231					4502		
135+00.00		144+00.00		4254						1431		
144+00.00		154+00.00		4293						1596		
154+00.00		213+00.00		6058								
981+00.00		995+00.00		6459						2153		
995+00.00		9+00.00		8170	198					2723		
5005+93.00	RT	5010+89.00		496								
5005+93.00	LT	5011+26.00									356	
5006+32.00	LT	5009+48.00		316								
5006+32.00	LT	5011+22.00		495								



USER NAME = .USERNAME.
 FILE NAME = #FILE#
 PLOT SCALE = 50.0000" / IN.
 PLOT DATE = 10/20/2011

DESIGNED -
 DRAWN - KRL
 CHECKED - PDS
 DATE - 10-21-2011

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N/A SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE. 90	SECTION (X2-1) R	COUNTY WINNEBAGO	TOTAL SHEETS 510	SHEET NO. 53
CONTRACT NO. 64C29				
ILLINOIS FED. AID PROJECT				