



**NOTES:**

1. ONLY STAGE 1 TRAFFIC PATTERN IS BEING SHOWN. DURING WINTER SHUT DOWN, TRAFFIC WILL BE RESUMED ON ALL EXISTING LANES.
2. EXISTING OVERHEAD SIGN STRUCTURE TO BE REMOVED DURING PRE-STAGE AND SIGN PANEL TEMPORARILY MOUNTED TO ROCKTON RD BRIDGE.
3. THE EXISTING SIGN CONTROLLER AND SIGN LUMINAIRES SHALL BE RELOCATED TO THE TEMPORARY LOCATION OF THE SIGN ATTACHED TO THE ROCKTON ROAD BRIDGE DURING CONSTRUCTION OF THIS PROJECT.
4. CONTRACTOR TO INSPECT CONDITION OF SIGN LUMINAIRES AND CONTROLLER PRIOR TO REMOVAL FROM EXISTING LOCATION, INSTALLATION ON TEMPORARY BRIDGE MOUNTS, REMOVAL FROM TEMPORARY LOCATIONS AND REINSTALLATION ON NEW SIGN STRUCTURE.
5. REFER TO ISTHA'S STANDARD H-10-00.

**LEGEND:**

- EXISTING UNIT DUCT
- - - PROPOSED UNIT DUCT
- ⊠ EXISTING LIGHT POLE TO REMAIN UNLESS NOTED OTHERWISE
- ⊠ EXISTING LIGHTING CONTROLLER
- PROPOSED HANDHOLE
- ⊙ TEMPORARY LIGHT POLE
- ⊠ TEMPORARY WOOD POLE
- ⊠ UNIT DUCT, 600V 2-1C NO.8, 1C NO.8 GROUND (XLP-TYPE USE) 2" DIA. CNC
- CONDUIT PUSHED, 4" DIA., PVC SCHEDULE 80 (PAID AS UNDERGROUND CONDUIT, PVC, 4" DIA.)



	LOCHNER FOR TOOLBOX, INC., CHICAGO, ILLINOIS	USER NAME = .USERNAME.	DESIGNED - BLM	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>TEMPORARY LIGHTING PLAN</b>		F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			PLOT SCALE = 5/8" = 1' / IN.	DRAWN - JPW		REVISED -	BRIDGE MOUNTED SIGN STRUCTURE STAGE 1 & WINTER SHUT DOWN	90	(X2-11R)	WINNEBAGO	510	266
		PLOT DATE = 10/25/2011	CHECKED - BLM	REVISED -	SCALE:      SHEET NO.      OF      SHEETS      STA.      TO STA.	CONTRACT NO. 64C29						
			DATE - 10/14/11	REVISED -	ILLINOIS FED. AID PROJECT							