



NOTES:

1. EXISTING OVERHEAD SIGN STRUCTURE TO BE REMOVED DURING PRE-STAGE.
2. TEMPORARY BRIDGE MOUNTED SIGN TO BE RELOCATED FROM STAGE 1/WINTER SHUT DOWN LOCATION.
3. THE EXISTING SIGN CONTROLLER AND SIGN LUMINAIRES SHALL BE RELOCATED TO THE TEMPORARY LOCATION OF THE SIGN ATTACHED TO THE ROCKTON ROAD BRIDGE DURING CONSTRUCTION OF THIS PROJECT.
4. CONTRACTOR TO INSPECT CONDITION OF SIGN LUMINAIRES AND CONTROLLER PRIOR TO REMOVAL FROM EXISTING LOCATION, INSTALLATION ON TEMPORARY BRIDGE MOUNTS, REMOVAL FROM TEMPORARY LOCATIONS AND REINSTALLATION ON NEW SIGN STRUCTURE.
5. REFER TO ISTHA'S STANDARD H-10-00.
6. EXTEND SIGN LIGHTING CONDUCTORS AND CONDUIT TO THE NEW LOCATION OF THE SIGN.

LEGEND:

- EXISTING UNIT DUCT
- - - PROPOSED UNIT DUCT
- ⊗ EXISTING LIGHT POLE TO REMAIN UNLESS NOTED OTHERWISE
- ⊠ EXISTING LIGHTING CONTROLLER
- PROPOSED HANDHOLE
- TEMPORARY LIGHT POLE
- TEMPORARY WOOD POLE
- CONDUIT PUSHED, 4" DIA., PVC SCHEDULE 80 (PAID AS UNDERGROUND CONDUIT, PVC, 4" DIA.)



USER NAME = _USERNAME_	DESIGNED - BLM	REVISED -
	DRAWN - JPW	REVISED -
PLOT SCALE = 50.0000' / IN.	CHECKED - BLM	REVISED -
PLOT DATE = 10/25/2011	DATE - 10/14/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TEMPORARY LIGHTING PLAN			
BRIDGE MOUNTED SIGN STRUCTURE STAGE 2			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.I. R.I.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	(X2-1)R	WINNEBAGO	510	267
CONTRACT NO. 64C29				
ILLINOIS FED. AID PROJECT				