



LEGEND:

GROUND MOUNTED SIGN

GUIDE SIGN SEQUENCE NUMBERING CODE

EXAMPLE

90-TR-22-(R)

REMOVE (APPLICABLE)

ROADWAY OR INTERCHANGE

90 - FAI ROUTE NUMBER
RR - ROCKTON ROAD RAMP

MOUNTING TYPE

SIGN PANEL NUMBER

- TR - TRUSS
- CL - CANTILEVER
- BR - BRIDGE MOUNTED
- WP - WOOD POLE
- TS - TELESCOPIC STEEL
- BS - BREAKAWAY STEEL
- CY - CANOPY WALL
- ST - STEEL TUBULAR

NOTE:
THE BLUE SPECIFIC SERVICE SIGNS ALONG THE I-90 MAINLINE SHALL REMAIN IN PLACE UNTIL SUCH TIME THAT REPLACEMENT SIGN HAS BEEN CONSTRUCTED. DUPLICATE ASSEMBLIES SHALL NOT EXIST FOR PERIODS IN EXCESS OF 24 HOURS.

NOTE:
THE POST SIZES & LENGTHS PROVIDED IN THE SIGNING SCHEDULE ARE FOR ESTIMATING PURPOSES ONLY. THE EXACT LENGTHS & SIZES SHALL BE DETERMINED AFTER THE SLOPES ARE AT FINAL GRADE.

NOTE:
AFTER THE FINAL GRADING IS COMPLETED, CONTACT KURT GLAZIER AT (815) 284-5478 OR KRISTIE NYDEREK AT (815) 284-5474 IN OPERATIONS FOR THE FINAL POST DESIGNS. IDOT SHALL HAVE 3 WEEKS TO PROVIDE THE FINAL POST DESIGNS AND LOCATIONS. PLEASE PROVIDE ENOUGH TIME IN THE SCHEDULE FOR THE DESIGN AND MATERIAL ORDERS.

NOTE:
RESIDENT ENGINEER SHALL CONDUCT A SIGN INVENTORY PRIOR TO BEGINNING OF CONSTRUCTION



SCALE: 1" = 50'-0"



USER NAME = ..USERNAME..	DESIGNED -	REVISED -
PLOT SCALE = 50,0000' / IN.	DRAWN - JDH	REVISED -
PLOT DATE = 10/19/2011	CHECKED - DW	REVISED -
	DATE - 10-21-2011	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**EXISTING AND PROPOSED SIGNING PLAN - WISCONSIN CROSSOVER
I-90 FROM WISCONSIN STATE LINE TO ROCKTON ROAD**

SCALE: 1"=50'-0" SHEET NO. 1 OF 9 SHEETS STA. 978+86 TO STA. 0+00

F.A.I. RTE. 90	SECTION (X2-1) R	COUNTY WINNEBAGO	TOTAL SHEETS 510	SHEET NO. 293
			CONTRACT NO. 64C29	
ILLINOIS FED. AID PROJECT				