

GENERAL NOTES

The final top four inches of soil in any right-of-way area disturbed by the Contractor must be capable of supporting vegetation. The soil must be from the A horizon (zero to 2' deep) of soil profiles of local soils.

All Borrow/Waste/Use sites must be approved by the Department prior to removing any material from the project or initiating any earthmoving activities, including temporary stockpiling outside the limits of construction.

The Contractor shall seed all disturbed areas within the project limits. Seeding Class 4 or 2A shall be used, except in front of properties where the grass will be mowed, then use Seeding, Class 1. Class 2A shall be used on front slopes and ditch bottoms. Class 4 shall be used behind Type A gutter, on all backslopes and areas behind the backslope, and beyond the toe of front slope on fill sections without ditches. This work will be included in the contract unit price per Square Yard for DECK SLAB REPAIR (PARTIAL)

Fertilizer shall be applied to all disturbed areas and incorporated into the seedbed prior to seeding or placement of sod at the rate specified in Sections 250 and 252 of the Standard Specifications. This work shall be included in the cost of DECK SLAB REPAIR (PARTIAL).

Mulch Method II shall be applied over all seeded areas. This shall be included in the cost of the DECK SLAB REPAIR (PARTIAL).

NO permits have been obtained to allow for the dropping of debris into the river. If any concrete or debris is dropped in the river, the contractor will be required to procure the proper permit(s) from the required Regulatory Agencies on their own. Any time delay or additional compensation due to the procuring of said permit(s) will not be given.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123.

INDEX OF SHEETS

1. Cover Sheet
2. Summary of quantities
3. General notes
4. District Standard 39.2
5. -10. Traffic Control Stage I
11. -16. Traffic Control Stage II
17. -30. Bridge Repair Plans

STANDARDS

- 701101-02 Off-Road Operations, Multilane, 4.5 m (15') to 600 mm (24") From Pavement Edge
- 701400-05 Approach to Lane Closure, Freeway/Expressway
- 701402-09 Lane Closure, Freeway/Expressway, with Barrier
- 701426-04 Lane Closure, Multilane, Intermittent or Moving Operation, for Speeds > 45 MPH
- 701901-02 Traffic Control Devices
- 704001-07 Temporary Concrete Barrier
- 720001-01 Sign Panel Mounting Details
- 720006-02 Sign Panel Erection Details
- 720011-01 Metal Posts for Signs, Markers and Delineators
- 728001-01 Telescoping Steel Sign Support
- 729001-01 Applications of Types A and B Metal Posts (For Signs & Markers)

FILE NAME =	USER NAME = Iinkd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	General Notes, Index of Sheets, Standards	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
D:\BRY\CADD plans\Rock Island County\231106\PLAN\eng.dgn		DRAWN -	REVISED -			280	181-1B/M-2	Rock Island	30	3	
PLOT SCALE = 50.0000 1/2 in.		CHECKED -	REVISED -			CONTRACT NO. 64F22					
PLOT DATE = Thu Oct 15 09:48:27 2011		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					