SUMMARY OF QUANTITIES

URBAN

SPECIALTY ITEM	SPECIAL PROV.	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	NEW SIDEWALK & SHARED USE PATH	STRUCTURAL: SN 047-8800	STRUCTURAL: SN 047-8801	STRUCTURAL: SN 047 -0051	STRUCTURAL: SN 047-2559	STRUCTURAL: SN 047-2541	WAUBONSEE DR TRAFFIC SIGNAL	MITCHELL DR TRAFFIC SIGNAL	LAKEWOOD SPRINGS DR TRAFFIC SIGNAL	SIGNAL INTER-CONNECT	EMERGENCY VEHICLE PRE-EMPTION	HIGHWAY LIGHTING
						FED =80%	FED =80%	FEDERAL = 80%					FED =80%	FEDERAL = 80%		FED =80%	FEDERAL = 0%	
						STATE = 20%	STATE = 0%	STATE = 20%					STATE = 10%	STATE = 13.4%		STATE = 20%	STATE = 0%	
						CITY = 0%	CITY = 20%	CITY = 0%					CITY = 10%	CITY = 6.6%		CITY = 0%	CITY = 100%	
								STRUCTURAL										
						0003	0028	0040	0040	0013	0040	0040	0021				0021	0021
		40603305	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N30	TON	1,259		1,259											
		40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	435	435												
		42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	68,476	68,476												
		42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1,072	1,072												
		42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	1,593	1,593												
		42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	636	636												
		42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	13,452	1,410	12,042											
		42400800	DETECTABLE WARNINGS	SQ FT	521	57	464											
	*	44000100	PAVEMENT REMOVAL	SQ YD	45,119	45,119												
		44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2,899	2,899												
		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	7,731	7,731												
		44000600	SIDEWALK REMOVAL	SQ FT	1,343	1,343												
		44003100	MEDIAN REMOVAL	SQ FT	1,169	1,169												
		44004250	PAVED SHOULDER REMOVAL	SQ YD	7,651	7,651												
		44200108	PAVEMENT PATCHING, TYPE II, 9 INCH	SQ YD	238	238												
		44200112	PAVEMENT PATCHING, TYPE III, 9 INCH	SQ YD	136	136												
		44200114	PAVEMENT PATCHING, TYPE IV, 9 INCH	SQ YD	103	103												
		44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	42	42												
	*	48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	808	808												
		48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	570	570												
		50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1						1							
		50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1					1								
		50102400	CONCRETE REMOVAL	CU YD	19.3					19.3								
		50105220	PIPE CULVERT REMOVAL	FOOT	1,127	992						135						
		50200100	STRUCTURE EXCAVATION	CU YD	1,466					200	1,075	191						
		50200300	COFFERDAM EXCAVATION	CU YD	176					176								
		50300225	CONCRETE STRUCTURES	CU YD	375.3			123.7	68.6	183.0								
		50300255	CONCRETE SUPERSTRUCTURE	CU YD	508.2					508.2								
		50300260	BRIDGE DECK GROOVING	SQ YD	989					989								
		50300265	SEAL COAT CONCRETE	CU YD	144					144								
		50300285	FORM LINER TEXTURED SURFACE	SQ FT	4,001			2,585	1,416									
		50300300	PROTECTIVE COAT	SQ YD	14,013			301	51	13,661								
		50400805	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 36 IN.	FOOT	1,113					1,113								
		50500505	STUD SHEAR CONNECTORS	EACH	462			314	148									
		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	151,430			14,230	7,330	129,870								
		50800515	BAR SPLICERS	EACH	532					532								
		50901720	BICYCLE RAILING	FOOT	343	83				222	38							

PB Americas, Inc.
230 WEST MONROE STREET.
SUITE 900
CHICAGO, IL. 60606
(312)782-8150

FILE NAME = duncanbd
PLOT SCALE = 20.0000 ' / in.
PLOT DATE = 10/19/2011

DESIGNED - MWS
DRAWN - MWS
CHECKED - KJB
DATE - 08-18-2011

REVISED - BDD 10-19-2011
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SOQ - 2 OF 9 | STA. | TO STA.

Rev.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
591	13R-2;14R-1 & BR-1(1);15R-1	KENDALL	429	5
	FINAL SUBMITTAL	CONTRACT NO. 66985		
	ILLINOIS FED. AID PROJECT			

s:\pw_work\pwidot\duncanbd\d0214252\D366985-SHT-500-revised.dgn