URBAN

SUMMARY OF QUANTITIES

SPECIALTY ITEM	SPECIAL PROV.	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	FED =80% STATE = 20% CITY = 0% ROADWAY	FED =80% STATE = 0% CITY = 20% NEW SIDEWALK & SHARED USE PATH	FEDERAL = 80% STATE = 20% CITY = 0% STRUCTURAL SN 047-8800	SN 047-8801	SN 047 -0051	SN 047-2559	SN 047-2541	FED =80% STATE = 10% CITY = 10% WAUBONSEE DR TRAFFIC SIGNAL	FEDERAL = 80% STATE = 13.4% CITY = 6.6% MITCHELL DR TRAFFIC SIGNAL	LAKEWOOD SPRINGS DR TRAFFIC SIGNAL	FED =80% STATE = 20% CITY = 0% SIGNAL INTER-CONNECT	FEDERAL = 0% STATE = 0% CITY = 100% EMERGENCY VEHICLE PRE-EMPTION	HIGHWAY LIGHTING
						0003	0028	0040	0040	0013	0040	0040	0021				0021	0021
		50901750	PARAPET RAILING	FOOT	726			319	185	222								
		51200959	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	630					630								
		51202600	DRIVING PILES	FOOT	630					630								
		51203200	TEST PILE METAL SHELLS	EACH	4					4								
		51500100	NAME PLATES	EACH	5			1	1	1	1	1						
		54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2						2							
		54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	2							2						
		54010603	PRECAST CONCRETE BOX CULVERTS 6' X 3'	FOOT	205.5							205.5						
		54011207	PRECAST CONCRETE BOX CULVERTS 12' X 7'	FOOT	114.3						114.3							
		54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	9	9												
		54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	3	3												
		54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	4	4												
		54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	7	7												
		54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2												
		54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1	1												
		54214515	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	1	1												
		5421A030	PIPE CULVERTS, CLASS A, TYPE 1 30" (TEMPORARY)	FOOT	51							51						
		5423D036	PIPE CULVERTS, CLASS D, TYPE 3 36" (TEMPORARY)	FOOT	525						525							
		54244805	INLET BOX, STANDARD 542501	EACH	2	2												
		54247110	GRATING FOR CONCRETE FLARED END SECTION 18"	EACH	4	4												
		54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	7	7												
		54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	2	2												
		54247190	GRATING FOR CONCRETE FLARED END SECTION 48"	EACH	1	1												
		54248150	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 30"	EACH	1	1												
		55100400	STORM SEWER REMOVAL 10"	FOOT	55	55												
		55100500	STORM SEWER REMOVAL 12"	FOOT	986	986												
		55100700	STORM SEWER REMOVAL 15"	FOOT	64	64												
		55101200	STORM SEWER REMOVAL 24"	FOOT	536	536												
		550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	655	655												
		550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	19	19												
		550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	63	63												
		550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	149	149												
		550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	8	8												
		550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	6,035	6,035												
		550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	1,158	1,158												
		550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	796	796												

PB Americas, Inc.
230 WEST MONROE STREET,
SUITE 900
CHICAGO, IL. 60606
(312)782-8150

FILE NAME = duncanbd	DESIGNED - MWS	REVISED -
	DRAWN - MWS	REVISED -
PLOT SCALE = 20.0000 '/ in.	CHECKED - KJB	REVISED -
PLOT DATE = 10/20/2011	DATE - 08-18-2011	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SOQ - 3 OF 9 | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
591	13R-2;14R-1 & BR-1(1);15R-1	KENDALL	429	6
	FINAL SUBMITTAL	CONTRACT NO. 66985		
	ILLINOIS FED. AID PROJECT			

c:\pw_work\pwidot\duncanbd\d0214252\D366985_SHT_SOQ-revised.dgn