


SUMMARY OF QUANTITIES

| SPECIALTY ITEM | SPECIAL PROV. | CODE NO. | DESCRIPTION | UNIT | TOTAL QUANTITY | URBAN | | | | | | | | | | | | | | |
|----------------|--------------------------------|------------|--|--------|----------------|-------------|-----------------------------|----------------------------|-----------------------------------|----------------------|-------------------------------|------------------|-------------|---------------|-------------|--------------|--|--|--|--|
| | | | | | | FED =80% | FED =80% | FEDERAL = 80% | | | | | FED =80% | FEDERAL = 80% | FED =80% | FEDERAL = 0% | | | | |
| | | | | | | STATE = 20% | STATE = 0% | STATE = 20% | | | | | STATE = 10% | STATE = 13.4% | STATE = 20% | STATE = 0% | | | | |
| | | | | | | CITY = 0% | CITY = 20% | CITY = 0% | | | | | CITY = 10% | CITY = 6.6% | CITY = 0% | CITY = 100% | | | | |
| ROADWAY | NEW SIDEWALK & SHARED USE PATH | STRUCTURAL | | | | | WAUBONSEE DR TRAFFIC SIGNAL | MITCHELL DR TRAFFIC SIGNAL | LAKWOOD SPRINGS DR TRAFFIC SIGNAL | SIGNAL INTER-CONNECT | EMERGENCY VEHICLE PRE-EMPTION | HIGHWAY LIGHTING | | | | | | | | |
| 0003 | 0028 | 0040 | 0040 | 0013 | 0040 | 0040 | | | | | | 0021 | 0021 | | | | | | | |
| | | 60240301 | INLETS, TYPE B, TYPE 8 GRATE | EACH | 1 | 1 | | | | | | | | | | | | | | |
| | | 60257900 | MANHOLES TO BE RECONSTRUCTED | EACH | 7 | 7 | | | | | | | | | | | | | | |
| | | 60300105 | FRAMES AND GRATES TO BE ADJUSTED | EACH | 5 | 5 | | | | | | | | | | | | | | |
| | | 60300305 | FRAMES AND LIDS TO BE ADJUSTED | EACH | 5 | 5 | | | | | | | | | | | | | | |
| | | 60500040 | REMOVING MANHOLES | EACH | 8 | 8 | | | | | | | | | | | | | | |
| | | 60500060 | REMOVING INLETS | EACH | 27 | 27 | | | | | | | | | | | | | | |
| | | 60602800 | CONCRETE GUTTER, TYPE B | FOOT | 319 | | | 319 | | | | | | | | | | | | |
| | | 60603800 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 | FOOT | 4,262 | 4,262 | | | | | | | | | | | | | | |
| | | 60605000 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 | FOOT | 26,025 | 26,025 | | | | | | | | | | | | | | |
| | | 60618300 | CONCRETE MEDIAN SURFACE, 4 INCH | SQ FT | 78,154 | 78,154 | | | | | | | | | | | | | | |
| | | 60618390 | CONCRETE MEDIAN SURFACE, CORRUGATED | SQ FT | 2,484 | 2,484 | | | | | | | | | | | | | | |
| | | 60619600 | CONCRETE MEDIAN, TYPE SB-6.12 | SQ FT | 125 | 125 | | | | | | | | | | | | | | |
| | | 60620000 | CONCRETE MEDIAN, TYPE SB-6.24 | SQ FT | 6,555 | 6,555 | | | | | | | | | | | | | | |
| | | 60625600 | ISLAND PAVEMENT (6") | SQ YD | 66 | 66 | | | | | | | | | | | | | | |
| △ | | 63100085 | TRAFFIC BARRIER TERMINAL, TYPE 6 | EACH | 3 | 3 | | | | | | | | | | | | | | |
| △ | | 63100167 | TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT | EACH | 3 | 3 | | | | | | | | | | | | | | |
| | | 63200310 | GUARDRAIL REMOVAL | FOOT | 2,556 | 2,556 | | | | | | | | | | | | | | |
| | | 63300705 | RUB RAIL | FOOT | 44 | 44 | | | | | | | | | | | | | | |
| | | 66400305 | CHAIN LINK FENCE, 6' | FOOT | 1,111 | 1,111 | | | | | | | | | | | | | | |
| | | 66407500 | CHAIN LINK GATES, 6' X 10' DOUBLE | EACH | 1 | 1 | | | | | | | | | | | | | | |
| △ | | 66900200 | NON-SPECIAL WASTE DISPOSAL | CU YD | 1,100 | 1,100 | | | | | | | | | | | | | | |
| △ | | 66900450 | SPECIAL WASTE PLANS AND REPORTS | L SUM | 1 | 1 | | | | | | | | | | | | | | |
| △ | | 66900530 | SOIL DISPOSAL ANALYSIS | EACH | 2 | 2 | | | | | | | | | | | | | | |
| | | 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 20 | 20 | | | | | | | | | | | | | | |
| | | 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | | | | | | | | | | | |
| | | 70100455 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701206 | L SUM | 1 | 1 | | | | | | | | | | | | | | |
| | | 70102630 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701601 | L SUM | 1 | 1 | | | | | | | | | | | | | | |
| | | 70102632 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701602 | L SUM | 1 | 1 | | | | | | | | | | | | | | |
| | | 70102625 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701606 | L SUM | 1 | 1 | | | | | | | | | | | | | | |
| | | 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1 | 1 | | | | | | | | | | | | | | |
| | | 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DA | 548 | 548 | | | | | | | | | | | | | | |
| | | 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 72 | 72 | | | | | | | | | | | | | | |
| | | 70300210 | TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS | SQ FT | 952 | 952 | | | | | | | | | | | | | | |
| | | 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 175,872 | 175,872 | | | | | | | | | | | | | | |
| | | 70300250 | TEMPORARY PAVEMENT MARKING - LINE 8" | FOOT | 6,446 | 6,446 | | | | | | | | | | | | | | |
| | | 70300260 | TEMPORARY PAVEMENT MARKING - LINE 12" | FOOT | 2,381 | 2,381 | | | | | | | | | | | | | | |

c:\p\work\p\work\duncanbd\021425\0366985-SHT-500-revised.dgn



FILE NAME = duncanbd
 DESIGNED - MWS
 DRAWN - MWS
 CHECKED - KJB
 DATE - 08-18-2011

REVISIONS
 REVISIONS
 REVISIONS
 REVISIONS

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SOQ - 5 OF 9 STA. TO STA.

| | | | | |
|---------------------------|-----------------------------|---------|--------------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 591 | 13R-2;14R-1 & BR-1(1);15R-1 | KENDALL | 429 | 8 |
| FINAL SUBMITTAL | | | CONTRACT NO. 66985 | |
| ILLINOIS FED. AID PROJECT | | | | |