


SUMMARY OF QUANTITIES

SPECIALTY ITEM	SPECIAL PROV.	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	URBAN														
						FED =80%	FED =80%	FEDERAL = 80%					FED =80%	FEDERAL = 80%	FED =80%	FEDERAL = 0%				
						STATE = 20%	STATE = 0%	STATE = 20%					STATE = 10%	STATE = 13.4%	STATE = 20%	STATE = 0%				
						CITY = 0%	CITY = 20%	CITY = 0%					CITY = 10%	CITY = 6.6%	CITY = 0%	CITY = 100%				
ROADWAY	NEW SIDEWALK & SHARED USE PATH	STRUCTURAL					WAUBONSEE DR TRAFFIC SIGNAL	MITCHELL DR TRAFFIC SIGNAL	LAKWOOD SPRINGS DR TRAFFIC SIGNAL	SIGNAL INTER-CONNECT	EMERGENCY VEHICLE PRE-EMPTION	HIGHWAY LIGHTING								
0003	0028	0040	0040	0013	0040	0040	0021					0021	0021							
		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	621	621														
	*	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	24,948	24,948														
		70400100	TEMPORARY CONCRETE BARRIER	FOOT	6,888	6,888														
		70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	4,293	4,293														
Δ		72000100	SIGN PANEL - TYPE 1	SQ. FT.	307	264								21.5	21.5					
Δ		72000200	SIGN PANEL - TYPE 2	SQ. FT.	78	28								20	30					
Δ		72400310	REMOVE SIGN PANEL - TYPE 1	SQ. FT.	155	155														
Δ		72400320	REMOVE SIGN PANEL - TYPE 2	SQ. FT.	13	13														
Δ		72400710	RELOCATE SIGN PANEL - TYPE 1	SQ. FT.	52	52														
Δ		72400720	RELOCATE SIGN PANEL - TYPE 2	SQ. FT.	20	20														
Δ		72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	91	91														
Δ		72900100	METAL POST - TYPE A	FOOT	174	174														
Δ		73000100	WOOD SIGN SUPPORT	FOOT	627	627														
Δ		73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	6	6														
Δ	*	78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	5,481	5,481														
Δ		78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,285	1,285														
Δ		78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	29,201	29,201														
Δ		78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	3,027	3,027														
Δ		78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	4,436	4,436														
Δ		78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	2,480	2,480														
Δ		78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	592	592														
Δ		78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	860	860														
Δ		78200300	PRISMATIC CURB REFLECTOR	EACH	421	421														
Δ		78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4														
	*	78300100	PAVEMENT MARKING REMOVAL	SQ FT	20,718	20,718														
Δ	*	80500010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	2									1	1					
Δ		81028320	UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	1319								553	432	334					
Δ		81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	3517								896	965	922	734				
Δ		81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	265									123	142					
Δ		81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	472									234	238					
Δ	*	81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	20								4	7	7	2				
Δ	*	81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	2									1	1					
Δ		81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	1273															1273
Δ		82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	6															6

c:\pwork\pwork\duncanb\40214252\0366985-SHT-500-revised.dgn



FILE NAME = duncanb	DESIGNED - MWS	REVISED - BDD 09-23-2011
PLOT SCALE = 20.0000' / 1"	DRAWN - MWS	REVISED -
PLOT DATE = 10/19/2011	CHECKED - KJB	REVISED -
	DATE - 08-18-2011	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE:                      SOO - 6 OF 9                      STA.                      TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
591	13R-2;14R-1 & BR-1(1);15R-1	KENDALL	429	9
FINAL SUBMITTAL			CONTRACT NO. 66985	
ILLINOIS FED. AID PROJECT				

Rev.