SUMMARY OF QUANTITIES

URBAN

SPECIALTY ITEM	SPECIAL PROV.	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	FED =80% STATE = 20% CITY = 0%	FED =80% STATE = 0% CITY = 20%	FEDERAL = 80% STATE = 20% CITY = 0%					FED =80% STATE = 10% CITY = 10%	FEDERAL = 80% STATE = 13.4% CITY = 6.6%		FED =80% STATE = 20% CITY = 0%	FEDERAL = 0% STATE = 0% CITY = 100%	
								STRUCTURAL										
						ROADWAY	NEW SIDEWALK & SHARED USE PATH	SN 047-8800	SN 047-8801	SN 047 -0051	SN 047-2559	SN 047-2541	WAUBONSEE DR TRAFFIC SIGNAL	MITCHELL DR TRAFFIC SIGNAL	LAKEWOOD SPRINGS DR TRAFFIC SIGNAL	SIGNAL INTER-CONNECT	EMERGENCY VEHICLE PRE-EMPTION	HIGHWAY LIGHTING
						0003	0028	0040	0040	0013	0040	0040	0021				0021	0021
△		84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	1													1
△	•	X8570225	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	2									1	1			
△	•	86000100	MASTER CONTROLLER	EACH	1											1		
△		86200300	UNINTERRUPTIBLE POWER SUPPLY, EXTENDED	EACH	2									1	1			
△		86400100	TRANSCEIVER - FIBER OPTIC	EACH	2											2		
△	•	87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	3253											3253		
△	•	87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	3189											3189		
△		87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2703								1046	808	849			
△		87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	4136								1102	850	891		1293	
△		87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	4413								973	1708	1732			
△		87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2060								645	698	717			
△		87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4985								1360	1847	1778			
△		87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	54									26	28			
△		87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	852									416	436			
△		87501200	TRAFFIC SIGNAL POST, 16 FT.	EACH	2									1	1			
△		87702890	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 32 FT.	EACH	1										1			
△		87702900	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 34 FT.	EACH	1									1				
△		87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT.	EACH	1									1				
△		87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT.	EACH	1										1			
△		87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT.	EACH	1										1			
△		87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1									1				
△		87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	1								1					
△		87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16									8	8			
△		87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8									4	4			
△	•	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	76									33	43			
△		87900200	DRILL EXISTING HANDHOLE	EACH	21								21					
△		88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	6									3	3			
△		88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	14								2	6	6			
△		88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	5								1	2	2			
△		88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4									2	2			
△		88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	20								8	6	6			
△		88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	29								3	13	13			
△	•	88500100	INDUCTIVE LOOP DETECTOR	EACH	16								2	7	7			
△		88600100	DETECTOR LOOP, TYPE I	FOOT	3853								1721	1070	1062			
△		88700200	LIGHT DETECTOR	EACH	6												6	
△		88700300	LIGHT DETECTOR AMPLIFIER	EACH	2												2	

PB Americas, Inc.
230 WEST MONROE STREET,
SUITE 900
CHICAGO, IL. 60606
(312)782-8150

FILE NAME = duncanbd	DESIGNED - MWS	REVISED -
	DRAWN - MWS	REVISED -
PLOT SCALE = 20.0000 ' / in.	CHECKED - KJB	REVISED -
PLOT DATE = 10/20/2011	DATE - 08-18-2011	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SOQ - 7 OF 9 | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
591	13R-2;14R-1 & BR-1(1);15R-1	KENDALL	429	10
	FINAL SUBMITTAL	CONTRACT NO. 66985		
	ILLINOIS FED. AID PROJECT			

c:\pw_work\pwidot\duncanbd\d0214282\D386985-SHT-SOQ-revised.dgn