

URBAN SUMMARY OF QUANTITIES

SPECIALTY ITEM	SPECIAL PROV.	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	FED =80%	FED =80%	FEDERAL = 80%					FED =80%	FEDERAL = 80%	FED =80%	FEDERAL = 0%
						STATE = 20%	STATE = 0%	STATE = 20%					STATE = 10%	STATE = 13.4%	STATE = 20%	STATE = 0%
						CITY = 0%	CITY = 20%	CITY = 0%					CITY = 10%	CITY = 6.6%	CITY = 0%	CITY = 100%
						ROADWAY	NEW SIDEWALK & SHARED USE PATH	STRUCTURAL			WAUBONSEE DR TRAFFIC SIGNAL	MITCHELL DR TRAFFIC SIGNAL	LAKWOOD SPRINGS DR TRAFFIC SIGNAL	SIGNAL INTER-CONNECT	EMERGENCY VEHICLE PRE-EMPTION	HIGHWAY LIGHTING
0003	0028	0040	0040	0013	0040	0040	0021			0021	0021					
		Z0023600	FILLING EXISTING CULVERTS	EACH	4	1					3					
		70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1										
		Z0026402	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	2,396			1,376	1,020							
		Z0026407	TEMPORARY SHEET PILING	SQ FT	540.0				540							
		64300750	IMPACT ATTENUATORS (SEVERE USE, NARROW), TEST LEVEL 2	EACH	1	1										
		Z0030280	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3	EACH	8	8										
		Z0030360	IMPACT ATTENUATORS, RELOCATE (SEVERE USE), TEST LEVEL 3	EACH	13	13										
Δ		Z0033056	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1									1		
		Z0041700	PLUG EXISTING STORM SEWERS	EACH	2	2										
		Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	647			318	185	144						
Δ		Z0054400	ROCK FILL	CU YD	235						134	101				
		Z0056618	STORM SEWER (WATER MAIN REQUIREMENTS) 27 INCH	FOOT	15	15										
		Z0056622	STORM SEWER (WATER MAIN REQUIREMENTS) 36 INCH	FOOT	22	22										
		Z0062456	TEMPORARY PAVEMENT	SQ YD	8,858	8,858										
		Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1,150						999	151				
Δ		Z0033043	RE-OPTIMIZE TEMPORARY TRAFFIC SIGNAL SYSTEM	EACH	1									1		
		X0327346	TEMPORARY AGGREGATE WEDGE	TON	258	258										
		X0327301	RELOCATE EXISTING MAIL BOX	EACH	7	7										
Δ		X6300120	STEEL PLATE BEAM GUARD RAIL, 6 FOOT POSTS, SPECIAL	FOOT	216	216										
⊙		Z0076600	TRAINEES	HOUR	2,500	2,500										

c:\pwwork\pwwork\pwwork\duncanbd\0214252\0366985-SHT-S00-revised.dgn



FILE NAME = duncanbd	DESIGNED - MWS	REVISED -
PLOT SCALE = 20.0000' / in.	DRAWN - MWS	REVISED -
PLOT DATE = 10/20/2011	CHECKED - KJB	REVISED -
	DATE - 08-18-2011	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SOQ - 9 OF 9 STA. TO STA.

F.A.P. RTE. 591	SECTION 13R-2;14R-1 & BR-1(1);15R-1	COUNTY KENDALL	TOTAL SHEETS 429	SHEET NO. 12
FINAL SUBMITTAL			CONTRACT NO. 66985	
[ILLINOIS] FED. AID PROJECT				

Rev.