SIGN SCHEDULE

			SIGN PANELS											TELESCOPING STEEL SIGN SUPPORT				METAL POST - TYPE A				WOOD SIGN SUPPORT			
SIGN NO.	STATION	LT/RT	"AA" (L.F.)	"BB" (L.F.)	WIDTH (L.F.)	DEPTH (L.F.)	EXIST TO REMAIN (SQ. FT.)	REMOVE SIGN PANEL, TYPE 1 (SQ. FT.)	REMOVE SIGN PANEL, TYPE 2 (SQ. FT.)	INSTALL SIGN PANEL TYPE 1 (SQ. FT.)	INSTALL SIGN PANEL TYPE 2 (SQ. FT.)	RELOCATE SIGN PANEL TYPE 1 (SQ. FT.)	RELOCATE SIGN PANEL TYPE 2 (SQ. FT.)	P1 (L.F.)	P2 (L.F.)	P3 (L.F.)	PAY LENGTH (L.F.)	P1 (L.F.)	P2 (L.F.)	P3 (L.F.)	PAY LENGTH (L.F.)	P1 (L.F.)	P2 (L.F.)	P3 (L.F.)	PAY LENGTH (L.F.)
								72400310	72400320	72000100	72000200	72400710	72400720	72800100				72900100				73000100			
S-1	9+75	RT	10.00	7.3	2.50	3.00				7.50												10.3			15.3
S-2	10+86	RT			3.00	3.00		9.00																	
S-3	13+17	LT	6.20	8.1	2.50	2.00						5.00										14.0			14.0
S-4	15+71	LT	11.00	9.7	2.50	3.00		5.00		7.50												10.3			15.3
S-5	16+58	RT			2.00	2.50		5.00																	
S-6	17+69	RT			3.00	3.00		9.00																	
S-7	30+72	RT			3.00	3.00		6.25		9.00															
S-8	30+72	RT	3.75	7.3	2.00	0.67		1.33		1.33												16.9			16.9
S-9	31+39	LT			2.00	2.50		5.00																	
S-10	31+39	LT			1.50	2.00		3.00																	
S-11	34+55	LT	9.18	7.0	2.50	2.50						6.25										16.5			16.5
S-12	36+73	LT			2.00	1.00		2.00		2.00															
S-13	36+73	LT	4.50	7.5	2.00	2.00		4.00		4.00												15.0			15.0
S-14	36+91	RT	11.98	7.2	1.50	1.50				2.25												14.1			14.1
S-15	36+97	RT			3.00	0.67						2.00													
S-16	36+97	RT	16.69	7.0	3.00	0.67						2.00		9.7			14.7								
S-17	37+44	LT	8.97	7.1	2.50	2.50		6.25		6.25												12.3			12.3
S-18	37+95	RT	9.10	7.2	2.50	2.50		6.25		6.25												12.3			12.3
S-19	38+10	RT	4.09	7.4	1.50	1.50				2.25												13.5			13.5
S-20	39+06	LT			2.00	2.50						5.00													
S-21	39+06	LT	8.85	7.0	2.00	0.50						1.00										15.9			15.9
S-22	40+37	RT			2.00	1.00		2.00		2.00															
S-23	40+37	RT	3.85	7.3	2.00	2.00		4.00		4.00												15.0			15.0
S-24	42+10	RT	10.50	7.2	2.00	2.50						5.00										14.5			14.5
S-25	44+09	RT			2.00	3.00						6.00													
S-26	44+09	RT			2.00	1.00						2.00													
S-27	44+09	RT	11.42	7.2	3.00	3.00						9.00										19.0			19.0
S-28	46+84	LT			3.00	3.00		9.00		9.00												17.3			17.3
S-29	46+84	LT	6.40	7.0	2.00	0.67		1.33		1.33															
S-30	47+75	RT	11.60	7.2	5.00	2.50			12.50		12.50											19.9	20.0		39.9
S-31	48+30	LT	6.40	7.0	2.50	2.00						5.00										15.4			15.4
S-32	48+90	RT			4.00	3.00		5.60																	
S-33	59+90	RT			3.00	3.00		6.25		9.00															
S-34	59+90	RT	6.86	7.3	4.00	0.67		2.68		2.68												15.7			15.7
S-35	62+00	LT	5.56	7.0	2.50	3.00				7.50															
S-36	64+41	RT	17.39	7.0	1.00	1.50				1.50								12.4			12.4				
S-37	64+50	LT			1.50	1.50				2.25															
S-38	64+50	LT			1.00	0.75				0.75															
S-39	64+50	LT	18.41	7.0	1.00	1.50				1.50								14.6			14.6				
S-40	64+50	LT			1.50	1.50				2.25															
S-41	64+50	LT			1.00	0.75				0.75															
S-42	64+50	LT	19.42	7.0	1.00	1.50				1.50								14.6			14.6				
S-43	65+71	RT			1.50	1.50				2.25															
S-44	65+71	RT			1.00	0.75				0.75															
S-45	65+71	RT	16.96	7.1	1.00	1.50				1.50								14.3			14.3				
S-46	65+75	RT			1.50	1.50				2.25															
S-47	65+75	RT			1.00	0.75				0.75															
S-48	65+75	RT	15.39	7.1	1.00	1.50				1.50								14.3			14.3				
S-49	65+83	LT	20.05	7.3	1.00	1.50				1.50								12.0			12.0				
S-50	66+98	RT	4.08	7.3	2.50	3.00				7.50												15.0			15.0
S-51	71+26	LT			1.25	0.67		0.83		0.83															
S-52	71+26	LT			1.25	0.67		0.83		0.83								7.3			7.3				
S-53	71+26	LT			1.25	0.67		0.83		0.83															
S-54	71+26	LT	11.27	7.6	1.25	0.67		0.83		0.83								7.3			7.3				
S-55	28+64	LT	5.00	7.7	2.00	2.50	5.00																		
Sheet 5 Sub Totals								**96.27**	**12.50**	**115.67**	**12.50**	**48.25**	**0.00**				**14.70**				**96.80**				**312.90**



SIGN POST INSTALLATION

EJM ENGINEERING, INC.
411 South Wells Street Suite 800
Chicago, Illinois 60607

PB Americas, Inc.
230 WEST MONROE STREET,
SUITE 900
CHICAGO, IL. 60606
(312)782-8150

FILE NAME =	DESIGNED - GR	REVISED -
	DRAWN - GR	REVISED -
PLOT SCALE = 1:50	CHECKED - BS	REVISED -
PLOT DATE = 5/20/2011	DATE - 4/8/2011	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGN SCHEDULE

SCALE: NTS | SHEET NO. 5 OF 6 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
591	13R-2;14R-1 & BR-1(1);15R-1	KENDALL	429	224
		CONTRACT NO. 66985		
	ILLINOIS	FED. AID PROJECT		

FINAL SUBMITTAL