

80% FEDERAL / 20% STATE		80% FED / 20% STATE			
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0004	BRIDGE 0011 SN 050-0255
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	62	62	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	56	56	
20101000	TEMPORARY FENCE	FOOT	594	594	
20200100	EARTH EXCAVATION	CU YD	301	301	
20300100	CHANNEL EXCAVATION	CU YD	1,378	1,378	
20400800	FURNISHED EXCAVATION	CU YD	2,201	2,201	
25000300	SEEDING, CLASS 3	ACRE	1	1	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90	
25100630	EROSION CONTROL BLANKET	SQ YD	905	905	
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	3,901	3,901	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	98	98	
28000305	TEMPORARY DITCH CHECKS	FOOT	381	381	
28000400	PERIMETER EROSION BARRIER	FOOT	594	594	
28100107	STONE RIPRAP, CLASS A4	SQ YD	3,513	1,323	2,190
28200200	FILTER FABRIC	SQ YD	3,513	1,323	2,190
35100100	AGGREGATE BASE COURSE, TYPE A	TON	25	25	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	255	255	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	83	83	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	480	480	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	329	329	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	173	173	
42001300	PROTECTIVE COAT	SQ YD	366	366	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	40	40	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	183	183	
44000100	PAVEMENT REMOVAL	SQ YD	223	223	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	21	21	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	589	589	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50105220	PIPE CULVERT REMOVAL	FOOT	80	80	
50200100	STRUCTURE EXCAVATION	CU YD	195		195
50200300	COFFERDAM EXCAVATION	CU YD	54		54
50201101	COFFERDAM (TYPE 1) (LOCATION - 1)	EACH	1		1
50201102	COFFERDAM (TYPE 1) (LOCATION - 2)	EACH	1		1
50300225	CONCRETE STRUCTURES	CU YD	246.5		246.5
50300255	CONCRETE SUPERSTRUCTURE	CU YD	343.3		343.3
50300260	BRIDGE DECK GROOVING	SQ YD	760		760
50300280	CONCRETE ENCASEMENT	CU YD	4.4		4.4
50300300	PROTECTIVE COAT	SQ YD	953		953
50400905	FURNISHING & ERECTING PRECAST PRESTRESSED CONC I-BEAMS, 42 IN	FOOT	822		822
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	101,890		101,890

80% FEDERAL / 20% STATE		80% FED / 20% STATE			
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0004	BRIDGE 0011 SN 050-0255
50800515	BAR SPLICERS	EACH	895		895
51201600	FURNISHING STEEL PILES, HP12X53	FOOT	1,457		1,457
51202305	DRIVING PILES	FOOT	1,457		1,457
51203600	TEST PILE STEEL, HP12X53	EACH	4		4
51204650	PILE SHOES	EACH	32		32
51500100	NAME PLATES	EACH	1		1
542A1057	PIPE CULVERTS, CLASS A, TYPE 2 12"	FOOT	80	80	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	85		85
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	512.5	512.5	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EA	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3	
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	1	1	
63200310	GUARDRAIL REMOVAL	FOOT	875	875	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	7	7	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1,104	1,104	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3,394	3,394	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	72	72	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,466	3,466	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	362.5	362.5	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	362.5	362.5	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3,602	3,602	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	7	7	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3	3	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	11	11	
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	15	15	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
Z0026407	TEMPORARY SHEET PILING	SQ FT	253		253
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	128		128
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	190		190
Z0073500	TEMPORARY SUPPORT SYSTEM	L SUM	1		1
X0327301	RELOCATE EXISTING MAILBOX	EACH	1	1	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	129		129
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1,480	1,480	
* Z0076600	TRAINERS	Hour	1000	1000	

\* SPECIALTY ITEM  
@ 0042

**benesch**  
engineers · scientists · planners  
Alfred Benesch & Company  
205 North Michigan Avenue, Suite 2400  
Chicago, Illinois 60601  
312-565-0450 Job No. 3938.11

FILE NAME =  
... \D366A28-shr-soq.dgn

USER NAME = tbenk  
DESIGNED - AE  
DRAWN - TMB  
CHECKED - JMM  
DATE - 10/20/11  
PLOT SCALE = NTS  
PLOT DATE = 10/20/2011

REVISED -  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: NTS SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE. 68	SECTION (3)BR-3	COUNTY LASALLE	TOTAL SHEETS 61	SHEET NO. 3
CONTRACT NO. 66A20				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				