

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	URBAN					
				0003 FED/STATE 80/20	0028 MULTI-USE PATHWAY FED/ST/CITY 80/10/10	0021 SIGNALS 80/10/10 <i>FED STATE CITY</i>	0040 CITY 100%	0040 FED/ST/CITY 80/10/10	0021 FED/STATE 80/20 URBAN
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	25,648	25,648					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	432	432					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	118	118					
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	194	194					
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	35,708	35,708					
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	2,482	2,482					
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	392	392					
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	349	349					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	17,726	17,726					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,675	2,675					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	2,475	2,475					
* 72000100	SIGN PANEL - TYPE 1	SQ FT	70			70			
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	3,666	3,666					
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	602	602					
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	18,273	18,273					
78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	3,468	3,468					
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	352	352					
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	356	356					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	416	416					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	6,893	6,893					
* 80500200	SERVICE INSTALLATION, TYPE B	EACH	2			1			1
* 81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	8,607			842			7,765
* 81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	276			276			
* 81028380	UNDERGROUND CONDUIT, PVC, 3 1/2" DIA.	FOOT	151			151			
* 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	5			5			
* 81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1			1			
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	2,704.5			1,758.0			946.5
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	4			4			
* 85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1			1			
* 86000105	MASTER CONTROLLER (SPECIAL)	EACH	1			1			
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1,966			1,966			
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2,430			2,430			

\* SPECIALTY ITEMS

FILE NAME K:\p\projects\2008023556\DDN\04-FileB\ch1-30-09.dwg	USER NAME 1001	DESIGNED DRAWN	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION			F.A.P. RTE. 399	SECTION 36 R-7	COUNTY TAZEWELL	TOTAL SHEETS 390	SHEET NO. 9
PLT BY DATE	SCALE DATE	CHECKED DATE	REVISED DATE	FAP 399 (IL RTE. 8) SUMMARY OF QUANTITIES			CONTRACT NO. 68370		ILLINOIS FED. AID PROJECT		
SCALE: NONE				SHEET NO. OF SHEETS STA.		TO STA.					