

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				0003 FED/STATE 80/20	0028 MULTI-USE PATHWAY FED/ST/CITY 80/10/10	0021 SIGNALS 80/10/10 FED/STATE CITY	0040 CITY 100%	0040 FED/ST/CITY 80/10/10	0021 FED/STATE 80/20 URBAN
Z0050600	REMOVE AND RESET ORNAMENTAL FENCE	FOOT	263	263					
Z0056648	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12"	FOOT	132					132	
Z0056650	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 15"	FOOT	73					73	
Z0056668	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 12"	FOOT	630				46	584	
Z0056669	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 15"	FOOT	741	535				206	
Z0056670	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 18"	FOOT	25					25	
Z0056672	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 24"	FOOT	40					40	
* Z0056900	SANITARY SEWER 8"	FOOT	175	74			101		
Z0062456	TEMPORARY PAVEMENT	SQ YD	4,461	4,461					
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	160	160					
* B2006216	TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	8	8					
X0320374	PLUG EXISTING SANITARY SEWERS	EACH	1				1		
X0322917	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	EACH	1	1					
X0322918	PROPOSED MANHOLE/CATCH BASIN CONNECTION OVER EXISTING STORM SEWER	EACH	2					2	
X0323389	STORM SEWER CONNECTION	EACH	2					2	
* X0323760	SANITARY SEWER SERVICE, 6" PVC, COMPLETE	EACH	1	1					
* X0323906	CAMERA POLE, 45 FT	EACH	1						1
* X0323909	DATA NETWORK PORT ADAPTER	EACH	2						2
* X0323920	POLE MOUNTED EQUIPMENT CABINET, TYPE B	EACH	1						1
X0324752	STORM SEWER TO BE FILLED	CU YD	2	2					
* X0325323	MANHOLES, TYPE A, SANITARY, 4' - DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2				2		
* X0326252	COMPUTER WORKSTATION	EACH	2						2
* X0326253	LCD MONITOR	EACH	4						4
* X0326255	APPLICATION SERVER	EACH	1						1
* X0326267	VIDEO SERVER	EACH	2						2
* X0326812	CAT 5 ETHERNET CABLE	FOOT	306						306
* X0326905	CLOSED-CIRCUIT TELEVISION DOME CAMERA, IP BASED	EACH	4						4
* X0326906	CLOSED-CIRCUIT TELEVISION DOME CAMERA, IP BASED (MATERIAL ONLY)	EACH	2						2
X2503110	MOWING (SPECIAL)	ACRE	7.50	7.50					
X4400110	TEMPORARY PAVEMENT REMOVAL	SQ YD	4,461	4,461					
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	428	428					
X6020082	INLETS, TYPE G-1	EACH	38					38	

NON-PART 100% STATE \* SPECIALTY ITEMS

FILE NAME X:\Mngmnt\2008\03\06\CON\14-11\11-11-11.dgn	USER NAME DDI	DESIGNED DPAWN	REVISED
PLT DATE 11/11/11	CHECKED	DATE 10-21-11	REVISED

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FAP 399 (IL RTE. 8)  
SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 399	SECTION 36 R-7	COUNTY TAZEWELL	TOTAL SHEETS 390	SHEET NO. 11
CONTRACT NO. 68370				
ILLINOIS FED. AID PROJECT				