

HANDRAIL REMOVAL				
LOCATION				FOOT
SCHOOL STREET				
STA. 12+72.20	TO	STA. 12+83.20	RT	35
TOTAL				35

REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL						GEOTECHNICAL FABRIC FOR GROUND STABILIZATION		SUB-BASE GRANULAR MATERIAL, TYPE C		EMBANKMENT**	
LOCATION						EST. DEPTH	EST. WIDTH	CU YD	SQ YD	CU YD	CU YD
ILLINOIS ROUTE 8											
STA. 222+55	TO	STA. 225+20		2'	74.1	1,404			2,105	1,404	
STA. 238+10	TO	STA. 240+27		2'	67.2	1,080			1,620	1,080	
STA. 240+27	TO	STA. 244+20		1'	38.6	558			*	*	558
STA. 244+20	TO	STA. 247+82		2'	67.2	1,801			2,702	1,801	
STA. 247+82	TO	STA. 253+72		0.67'	38.1	555			*	*	555
STA. 253+72	TO	STA. 259+77		2'	67.2	3,010			4,515	3,010	
STA. 259+77	TO	STA. 260+95		2'	82.3	720			1,080	720	
TOTAL						9,128			12,022	8,015	1,113

* UNSUITABLE MATERIAL THESE LOCATIONS TO BE REPLACED WITH EMBANKMENT
 ** QUANTITY PROVIDED FOR INFORMATION ONLY - SEE EARTHWORK SUMMARY FOR AVAILABLE EMBANKMENT

REMOVING INLETS		
LOCATION		EACH
ILLINOIS ROUTE 8		
STA. 209+76.57	LT	1
STA. 214+59.44	LT	1
STA. 214+69.95	LT	1
STA. 224+91.48	RT	1
STA. 225+94.06	RT	1
STA. 226+12.70	RT	1
STA. 232+92.68	RT	1
TOTAL		7

TEMPORARY EROSION CONTROL SEEDING		
LOCATION		POUND
ILLINOIS ROUTE 8		
SCHOOL STREET		40
TOTAL		660

TEMPORARY DITCH CHECKS		
STAGE I LOCATION		FEET
IL. ROUTE 8		
STA. 206+74.51	LT	8
STA. 208+25.13	LT	13
STA. 209+74.76	LT	8
STA. 211+24.71	LT	6
STA. 212+74.93	LT	8
STA. 213+74.17	LT	13
STA. 215+67.14	LT	8
STA. 216+27.11	LT	8
STA. 217+01.94	LT	13
STA. 217+77.14	LT	13
STA. 218+52.42	LT	13
STA. 219+27.24	LT	13
STA. 220+02.25	LT	13
STA. 220+40.35	LT	13
STA. 220+77.95	LT	13
STA. 221+16.16	LT	13
STA. 221+54.17	LT	8
STA. 221+92.18	LT	8
STA. 288+50.00	LT	13
STA. 288+00.00	LT	13
STA. 289+00.00	LT	13
SCHOOL ST.		
STA. 13+00.00	LT	13
STA. 13+20.00	LT	13
STA. 13+40.00	LT	13
STA. 13+70.50	LT	13
STA. 14+11.11	RT	13
STA. 14+67.47	RT	13
STA. 14+85.88	LT	13
STAGE I SUB-TOTAL		322

INLET AND PIPE PROTECTION		
STAGE I LOCATION		EACH
IL. ROUTE 8		
STA. 201+45.00	LT	1
STA. 203+25.88	LT	1
STA. 204+91.00	LT	1
STA. 206+00.00	LT	1
STA. 208+00.03	LT	1
STA. 208+96.45	LT	1
STA. 208+93.83	LT	1
STA. 208+99.08	LT	1
STA. 209+59.99	LT	1
STA. 210+50.00	LT	1
STA. 210+50.00	LT	1
STA. 211+90.00	LT	1
STA. 213+30.00	LT	1
STA. 215+20.09	LT	1
STA. 216+00.00	LT	1
STA. 216+00.00	LT	1
STA. 218+00.00	LT	1
STA. 218+00.00	LT	1
STA. 220+00.00	LT	1
STA. 222+00.00	LT	1
STA. 224+29.80	LT	1
STA. 225+50.00	LT	1
STA. 227+81.11	LT	1
STA. 232+10.00	LT	1
STA. 228+85.51	LT	1
STA. 231+00.01	LT	1
STA. 233+00.00	LT	1
STA. 235+00.02	LT	1
STA. 237+29.97	LT	1
STA. 239+50.02	LT	1
STA. 240+99.95	LT	1
STA. 241+89.97	LT	1
STA. 242+99.97	LT	1
STA. 244+30.02	LT	1
STA. 245+29.97	LT	1
STA. 246+54.97	LT	1
STA. 248+00.03	LT	1
STA. 248+85.00	LT	1
STA. 251+21.72	LT	1
STA. 251+61.18	LT	1
STA. 252+03.22	LT	1
STA. 252+40.81	LT	1
STA. 254+00.00	LT	1
STA. 256+00.00	LT	1
STA. 258+00.03	LT	1
STA. 260+00.00	LT	1
STA. 263+75.00	LT	1
STA. 265+10.00	LT	1
STA. 266+10.00	LT	1
STA. 267+20.00	LT	1
STA. 268+30.00	LT	1
STA. 269+25.91	LT	1
STA. 269+27.00	LT	1
STA. 270+10.00	LT	1
SCHOOL STREET		
STA. 11+10.00	RT	1
STA. 11+23.50	CL	1
STA. 11+23.50	LT	1
STA. 12+06.46	RT	1
STA. 12+77.73	LT	1
STA. 12+77.76	RT	1
STA. 12+93.09	RT	1
STA. 13+50.00	RT	1
STA. 14+68.13	LT	1
STAGE I SUB-TOTAL		63
STAGE III LOCATION		
IL. ROUTE 8		
STA. 202+69.40	RT	1
STA. 204+54.00	RT	1
STA. 207+04.02	RT	1
STA. 208+00.00	RT	1
STA. 208+93.83	RT	1
STA. 208+97.00	RT	1
STA. 208+99.08	RT	1
STA. 209+60.02	RT	1
STA. 210+50.00	RT	1
STA. 210+50.05	RT	1
STA. 211+90.00	RT	1
STA. 213+30.00	RT	1
STA. 215+22.57	RT	1
STAGE III SUB-TOTAL		299
TOTAL		621

INLET AND PIPE PROTECTION		
STAGE III LOCATION		EACH
IL. ROUTE 8		
STA. 215+50.00	RT	1
STA. 215+99.99	RT	1
STA. 216+00.00	RT	1
STA. 217+39.96	RT	1
STA. 217+40.00	RT	1
STA. 218+69.97	RT	1
STA. 218+70.02	RT	1
STA. 220+80.00	RT	1
STA. 222+40.00	RT	1
STA. 222+40.10	RT	1
STA. 223+90.00	RT	1
STA. 225+00.00	RT	1
STA. 226+12.75	RT	1
STA. 226+15.00	RT	1
STA. 226+81.10	RT	1
STA. 228+27.02	RT	1
STA. 228+54.23	RT	1
STA. 230+96.87	RT	1
STA. 232+25.00	RT	1
STA. 232+25.09	RT	1
STA. 232+84.00	RT	1
STA. 234+19.88	RT	1
STA. 234+20.00	RT	1
STA. 235+24.97	RT	1
STA. 238+99.95	RT	1
STA. 238+96.94	RT	1
STA. 239+99.84	RT	1
STA. 240+51.98	RT	1
STA. 240+69.52	RT	1
STA. 241+06.95	RT	1
STA. 243+00.00	RT	1
STA. 244+80.01	RT	1
STA. 246+16.79	RT	1
STA. 247+29.98	RT	1
STA. 247+30.00	RT	1
STA. 248+26.49	RT	1
STA. 248+44.05	RT	1
STA. 248+78.12	RT	1
STA. 249+82.00	RT	1
STA. 249+82.01	RT	1
STA. 250+64.22	RT	1
STA. 250+68.02	RT	1
STA. 251+64.93	RT	1
STA. 252+03.22	RT	1
STA. 252+08.26	RT	1
STA. 252+45.21	RT	1
STA. 252+80.89	RT	1
STA. 253+39.02	RT	1
STA. 255+10.02	RT	1
STA. 255+10.05	RT	1
STA. 256+36.96	RT	1
STA. 256+70.12	RT	1
STA. 257+10.60	RT	1
STA. 257+60.06	RT	1
STA. 258+50.00	RT	1
STA. 260+00.00	RT	1
STA. 263+78.20	RT	1
STA. 264+70.00	RT	1
STA. 265+60.00	RT	1
STA. 266+50.00	RT	1
STA. 267+40.00	RT	1
STA. 268+30.00	RT	1
STA. 269+25.94	LT	1
STA. 269+29.00	RT	1
STA. 269+30.40	RT	1
STA. 270+10.00	RT	1
STA. 270+90.00	RT	1
SCHOOL STREET		
STA. 5+05.00	LT	1
STA. 6+22.00	LT	1
STA. 8+96.50	LT	1
STA. 8+97.00	RT	1
STAGE III SUB-TOTAL		84
TOTAL		147

TEMPORARY RAMP		
LOCATION	SQ YD	
SCHOOL ST		
STA 3+93.25	10.0	
RT STA 6+35.00 (GRANT ST)	11.0	
STA 7+60.00	17.5	
STA 13+25.00	15.5	
STA 16+24.00	10.0	
GRANT ST	12.0	
VOHLAND ST	12.0	
McGINLEY RD	12.0	
ESKEN DR	12.0	
WAGNER ST	12.0	
ERNEST ST		
STA 8+74.58	12.0	
STA 9+30.53	12.0	
TOTAL		148.0

FENCE REMOVAL				
LOCATION				FOOT
ILLINOIS ROUTE 8				
STA. 239+19.40	TO	STA. 239+58.40	LT	106
STA. 241+47.20	TO	STA. 242+00.00	LT	103
STA. 242+00.00	TO	STA. 242+51.25	LT	77
STA. 242+71.00	TO	STA. 244+87.50	LT	283
STA. 250+38.70	TO	STA. 251+44.50	LT	128
TOTAL				697

NITROGEN FERTILIZER NUTRIENT			
LOCATION	ACRE	LB/AC	POUNDS
ILLINOIS ROUTE 8	6.2	90.0	555
SCHOOL STREET	0.4	90.0	36
TOTAL			591

PHOSPHORUS FERTILIZER NUTRIENT			
LOCATION	ACRE	LB/AC	POUNDS
ILLINOIS ROUTE 8	6.2	90.0	555
SCHOOL STREET	0.4	90.0	36
TOTAL			591

POTASSIUM FERTILIZER NUTRIENT			
LOCATION	ACRE	LB/AC	POUNDS
ILLINOIS ROUTE 8	6.2	90.0	555
SCHOOL STREET	0.4	90.0	36
TOTAL			591

BUILDING REMOVAL			
LOCATION		L SUM	
NO. 1	STA. 251+00.00	LT	1
TOTAL		1	

REMOVAL AND DISPOSAL OF ASBESTOS, BUILDING NO. 1	FRIABLE	NON-FRIABLE
	L SUM	L SUM
	1	1

TOPSOIL SUMMARY		TOPSOIL EXCAVATION AND PLACEMENT	TOPSOIL REQUIRED	TOPSOIL FURNISHED AND PLACED 4"	
LOCATION		CU YD	CU YD	CU YD	SQ YD
MAINLINE STATION 240+00 TO 243+50 - 16" DEPTH					
		625.5			
MAINLINE STATION 253+50 TO 255+00 - 20" DEPTH					
		384.8			
MAINLINE STATION 280+25 TO 289+25 - 8" DEPTH					
		1,038.3			
MAINLINE STATION 200+00 TO 228+00					
			968.69		
MAINLINE STATION 228+00 TO 248+00					
			447.16		
MAINLINE STATION 248+00 TO 271+00					
			1,015.29		
SCHOOL STREET					
			273.81		
SUBTOTAL		2,048.5	2,705.0	656.4	5,908.0
TOTAL		2,049	2,705	656	5,908