

PAVEMENT MARKINGS	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	GROOVING FOR RECESSED PAVEMENT MARKING 7"	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	EPOXY PAVEMENT MARKING - LINE 4"			EPOXY PAVEMENT MARKING - LINE 8"		EPOXY PAVEMENT MARKING - LINE 12"		EPOXY PAVEMENT MARKING - LINE 24"	
				WHITE SKIP	WHITE SKIP DASH	WHITE	YELLOW	YEL. SKIP	WHITE	DIAGONAL 20' O.C.		STOP BAR
										WHITE	WHITE SKIP	YELLOW
LOCATION	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT		
ILLINOIS ROUTE 8												
STA. 194+00 TO STA. 200+00	83	83	35.2	142	36		385		17	55		
STA. 200+00 TO STA. 206+00	247	247	70.4	1,272	93		520		23	57		
STA. 206+00 TO STA. 212+00	300	300	26.4	411	63							
STA. 212+00 TO STA. 218+00	300	300	35.2	957			634			74		
STA. 218+00 TO STA. 224+00	300	300	17.6	322	81							
STA. 224+00 TO STA. 230+00	227	227	52.8	916	24		1,118	103	46	107		
STA. 230+00 TO STA. 236+00	300	300	35.2	1,201	256							
STA. 236+00 TO STA. 242+00	300	300	52.8	1,200	300							
STA. 242+00 TO STA. 248+00	300	300	52.8	1,200	300							
STA. 248+00 TO STA. 254+00	300	300	52.8	1,200	300							
STA. 254+00 TO STA. 260+00	300	300	52.8	1,200	300							
STA. 260+00 TO STA. 266+00	300	300	35.2	1,200	300							
STA. 266+00 TO STA. 272+00	165	165		339		285			118			
STA. 272+00 TO STA. 278+00	150	150				294						
STA. 278+00 TO STA. 284+00	94	94										
SCHOOL STREET												
STA. 3+85.00 TO STA. 10+00.00			47.0	1,402	29	633	280		74	26		
STA. 10+00.00 TO STA. 16+30.00			35.2	1,404	32	581	428		74	37		
SUBTOTAL	3,666	3,666	601.4	14,366	2,114	1,793	3,365	103	266	86	358	
TOTAL	3,666	3,666	602	18,273			3,468		352		358	

RAISED REFLECTIVE PAVEMENT MARKER			ONE-WAY CRYSTAL	TWO-WAY AMBER
LOCATION			EACH	
ILLINOIS ROUTE 8				
STA. 194+00.00	TO	STA. 200+00.00	5	4
STA. 200+00.00	TO	STA. 206+00.00	14	10
STA. 206+00.00	TO	STA. 212+00.00	16	8
STA. 212+00.00	TO	STA. 218+00.00	16	
STA. 218+00.00	TO	STA. 224+00.00	16	9
STA. 224+00.00	TO	STA. 230+00.00	13	4
STA. 230+00.00	TO	STA. 236+00.00	16	26
STA. 236+00.00	TO	STA. 242+00.00	16	30
STA. 242+00.00	TO	STA. 248+00.00	16	30
STA. 248+00.00	TO	STA. 254+00.00	16	30
STA. 254+00.00	TO	STA. 260+00.00	16	30
STA. 260+00.00	TO	STA. 266+00.00	16	30
STA. 266+00.00	TO	STA. 272+00.00	9	
STA. 272+00.00	TO	STA. 278+00.00	8	
STA. 278+00.00	TO	STA. 284+00.00	5	
SCHOOL STREET				
STA. 3+83.25	TO	STA. 5+05.60		3
STA. 14+99.50	TO	STA. 16+25.00		4
TOTAL			416	

TEMPORARY SIGN PANEL ASSEMBLY		
LOCATION		SQ FT
ILLINOIS ROUTE 8		
STA. 202+23.00	RT	16.00
STA. 205+43.00	RT	16.00
STA. 207+42.00	RT	16.00
STA. 223+48.00	RT	16.00
STA. 224+35.00	RT	16.00
STA. 238+59.00	RT	16.00
STA. 240+50.00	RT	16.00
STA. 245+78.00	RT	16.00
STA. 202+91.00	LT	16.00
STA. 204+55.00	LT	16.00
STA. 223+91.00	LT	16.00
STA. 236+89.00	LT	16.00
STA. 238+02.00	LT	16.00
STA. 246+21.00	LT	16.00
SCHOOL ST.		
STA. 6+50.00	RT	16.00
STA. 7+95.00	LT	16.00
STA. 8+20.00	RT	16.00
STA. 11+69.00	LT	16.00
STA. 14+20.00	LT	16.00
TOTAL		304

SANITARY SEWER SCHEDULE				PLUG EXISTING SANITARY SEWERS	SANITARY SEWER SERVICE, 6" PVC, COMPLETE	MANHOLES, TYPE A, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	SANITARY SEWER 8"
LOCATION				EACH	EACH	EACH	FOOT
ILLINOIS ROUTE 8							
STA. 251+24.76			43.18'	RT		1	
STA. 251+24.76	RT	TO	STA. 11+25.00	CL			170
ESKEN							
STA. 10+70.00				LT	1		
STA. 11+18.00	CL	TO	STA. 11+25.00	CL			5
STA. 11+18.00				CL	1		
STA. 11+25.00				CL		1	
TOTAL				1	1	2	175

REMOVE AND RESET ORNAMENTAL FENCE			
LOCATION			FOOT
ILLINOIS ROUTE 8			
STA. 247+10.00	TO	STA. 248+00.00	RT 91
STA. 255+53.00	TO	STA. 256+87.30	RT 172
TOTAL			283

TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	
LOCATION	EACH
ENTIRE PROJECT	8
TOTAL	8

CONSTRUCTION LAYOUT	
LOCATION	L SUM
ENTIRE PROJECT	1
TOTAL	1