

| CODE NO. | SUMMARY OF QUANTITIES ITEM | UNIT | TOTAL QUANTITY | 80% FED 20% STATE CONSTRUCTION CODE | |
|------------|---|-------|-------------------|---|----------------|
| | | | | ROADWAY 0001 | BRIDGE 0008 |
| 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER) | UNIT | 247 | 247 | |
| 20100210 | TREE REMOVAL (OVER 15 UNITS DIAMETER) | UNIT | 562 | 562 | |
| 20100500 | TREE REMOVAL, ACRES | ACRE | 2.7 | 2.7 | |
| 20200100 | EARTH EXCAVATION | CU YD | 174,758 | 174,758 | |
| 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL | CU YD | 7,503 | 7,503 | |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 59,340 | 59,340 | |
| * 25000210 | SEEDING, CLASS 2A | ACRE | 11 | 11 | |
| * 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 632 | 632 | |
| * 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 632 | 632 | |
| * 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 632 | 632 | |
| * 25100115 | MULCH, METHOD 2 | ACRE | 11 | 11 | |
| * 25100635 | HEAVY DUTY EROSION CONTROL BLANKET | SQ YD | 43,956 | 43,956 | |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | 2,107 | 2,107 | |
| 28000315 | AGGREGATE DITCH CHECKS | TON | 901 | 901 | |
| 28000400 | PERIMETER EROSION BARRIER | FOOT | 1,480 | 1,480 | |
| 28000500 | INLET AND PIPE PROTECTION | EACH | 5 | 5 | |
| 28100707 | STONE DUMPED RIPRAP, CLASS A4 | SQ YD | 6,471 | 6,471 | |
| 28100725 | STONE DUMPED RIPRAP, CLASS B3 | SQ YD | 1,899 | 1,899 | |
| 28200200 | FILTER FABRIC | SQ YD | 8,369 | 8,369 | |
| 35100700 | AGGREGATE BASE COURSE, TYPE A 8" | SQ YD | 3,054 | 3,054 | |
| 35800100 | PREPARATION OF BASE | SQ YD | 2,198 | 2,198 | |
| 35800200 | AGGREGATE BASE REPAIR | TON | 937 | 937 | |

* SPECIALTY ITEM

| | | | |
|---|-------------------------|-----------------|-----------|
| FILE NAME = | USER NAME = joloon | DESIGNED - JRB | REVISED - |
| W:\Transportation\2891\1250H (ADAMS) PLAN | S:\ADAMS\0001.dgn | DRAWN - TJD | REVISED - |
| | PLOT SCALE = 2.00 / IN. | CHECKED - | REVISED - |
| | PLOT DATE = 10/28/2011 | DATE - 10/20/11 | REVISED - |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**TR 1250N (WEST ADAMS STREET EXTENSION)
SUMMARY OF QUANTITIES**

SCALE: 1"=1' SHEET NO. 1 OF 4 SHEETS STA. N/A TO STA. N/A

| | | | | |
|---------------------------|----------|-----------|--------------------|--------------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 407 | 55-3HB-1 | MCDONOUGH | 103 | 4 |
| | | | CONTRACT NO. 68A41 | |
| ILLINOIS FED. AID PROJECT | | | | |