

80% FED.  
20% STATE

CODE NO.	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY 0001	BRIDGE 0008
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	409	409	
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	11	11	
40300400	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	TON	32	32	
40300500	COVER COAT AGGREGATE	TON	132	132	
40300600	SEAL COAT AGGREGATE	TON	66	66	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	107	107	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	266	266	
50105220	PIPE CULVERT REMOVAL	FOOT	219	219	
50200100	STRUCTURE EXCAVATION	CU YD	460		460
50300225	CONCRETE STRUCTURES	CU YD	128		128
50300255	CONCRETE SUPERSTRUCTURE	CU YD	353		353
50300260	BRIDGE DECK GROOVING	SQ YD	875		875
50300280	CONCRETE ENCASEMENT	CU YD	4.2		4.2
50300300	PROTECTIVE COAT	SQ YD	1,075		1,075
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	2,430		2,430
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	114,580		114,580
50800515	BAR SPLICERS	EACH	68		68
51100100	SLOPE WALL 4 INCH	SQ YD	254		254
51201610	FURNISHING STEEL PILES HP12x63	FOOT	445		445
51202305	DRIVING PILES	FOOT	445		445
51203610	TEST PILE STEEL HP12x63	EACH	2		2
51500100	NAME PLATES	EACH	1		1

\* SPECIALTY ITEM

FILE NAME =	USER NAME = jolson	DESIGNED - JRB	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>TR 1250N (WEST ADAMS STREET EXTENSION) SUMMARY OF QUANTITIES</b>		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
V:\Transportation\2891\1250N (ADAMS) PLAN	S:\ADAMS\SS0001.dgn	DRAWN - TJD	REVISED -		SCALE: 1=1	SHEET NO. 2 OF 4 SHEETS	STA. N/A	TO STA. N/A	407	55-3HB-1	McDONOUGH	103 5
	PLOT SCALE = 2.00 / 1/4	CHECKED -	REVISED -									CONTRACT NO. 68A41
	PLOT DATE = 10/26/2011	DATE - 10/20/11	REVISED -									ILLINOIS FED. AID PROJECT