

GUARDRAIL SCHEDULE					
STATION TO STATION	SIDE	STEEL PLATE BEAM GUARDRAIL, TYPE A	TRAFFIC BARRIER TERMINALS		TERMINAL MARKER DIRECT APPLIED
			TYPE 1, SPECIAL (TANGENT)	TYPE 6	
		FOOT	EACH		
1010+74.17 TO 1011+69.82	LT		1	1	1
1010+53.97 TO 1011+74.62	RT	25	1	1	1
1013+97.34 TO 1015+17.99	LT	25	1	1	1
1014+02.14 TO 1014+97.79	RT		1	1	1
TOTALS		50	4	4	4
USE		50	4	4	4

PERMANENT SURVEY MARKERS					
STATION	SIDE	PERMANENT SURVEY MARKERS		PERMANENT SURVEY TIES	
		TYPE I	(SPECIAL)		
		EACH			
1006+32.37	LT		1	4	
1013+89.00	RT	1			
TOTALS		1	1	4	
USE		1	1	4	

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS			
STATION	OFFSET	SIDE	EACH
TR 1250N WEST ADAMS STREET EXTENSION			
1004+50	28.13	LT	1
1004+50	31.87	RT	1
1005+00	40.00	LT	1
1005+00	40.00	RT	1
1006+00	40.00	RT	1
1006+25	50.00	RT	1
1006+50	40.00	LT	1
1007+00	50.00	RT	1
1008+00	100.00	LT	1
1009+50	275.00	LT	1
1010+87.86	205.00	RT	1
1016+50	120.00	LT	1
1016+90	205.00	RT	1
1016+90	265.00	RT	1
1018+25	60.00	LT	1
1018+64.98	78.57	RT	1
1018+75	290.00	RT	1
1019+00	60.00	LT	1
1019+00	50.00	RT	1
1019+02.95	140.00	RT	1
1020+03.50	34.12	LT	1
1020+25.00	25.86	RT	1
FAP 315 (IL 336)			
620+00	133.33	LT	1
620+00	120.00	RT	1
621+29.65	141.97	LT	1
621+43.92	251.39	LT	1
622+86.67	170.00	RT	1
626+36.71	160.00	RT	1
627+00	150.00	RT	1
628+19.44	160.00	LT	1
628+50	150.00	RT	1
TOTAL			31
USE			31

GUARDRAIL AND BARRIER WALL MARKERS			
STATION TO STATION	SIDE	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE C
		EACH	
1010+53.97 TO 1014+97.79	RT	4	3
1010+74.17 TO 1015+17.99	LT	4	3
TOTALS		8	6
USE		8	6

REMOVE EXISTING SEPTIC TANK			
STATION	OFFSET	SIDE	TOTAL
	FOOT		EACH
1011+88.00	147.80	RT	1
1013+91.60	130.90	LT	1
1014+13.60	130.90	LT	1
TOTAL			3
USE			3

BUILDING AND FOUNDATION REMOVAL				
STATION	SIDE	BUILDING REMOVAL		FOUNDATION REMOVAL
		NUMBER	L SUM	EACH
1012+00	RT	1	1	
1012+25	LT	2	1	
1013+57	LT			1
TOTAL			2	1
USE			2	1

GUARDRAIL AGGREGATE EROSION CONTROL			
STATION TO STATION	SIDE	GUARDRAIL AGGREGATE EROSION CONTROL	TON
TR 1250N (ADAMS ST EXT)			
1010+19.97	1011+87.12	RT	17
1010+40.17	1011+82.32	LT	14
1013+84.84	1015+51.99	LT	14
1013+89.64	1015+31.79	RT	17
TOTAL			62
USE			62

SEDIMENT BASIN			
LOCATION	SIDE	OFFSET	SEDIMENT BASIN EACH
TR 1250N (ADAMS ST EXT)			
STA 1010+27.18	RT	153.76'	1
STA 1017+52.74	RT	161.73'	1
TOTAL			2
USE			2

SEALING ABANDONED WATER WELLS			
STATION	OFFSET	SIDE	TOTAL
	FOOT		EACH
1012+13.10	133.80	RT	1
1012+27.12	217.80	LT	1
1013+41.30	176.20	LT	1
TOTAL			3
USE			3

FENCE REMOVAL			
STATION TO STATION	SIDE	LENGTH	
		LT/RT	FOOT
1006+35	1012+05	LT	570
1008+75	1008+90	RT	95
1008+90	1010+75	RT	185
1010+75	1011+15	RT	130
1012+85	1020+25	RT	740
1015+85	1017+40	RT	290
1017+00	1020+00	LT	300
620+00	621+15	LT	115
621+15	621+35	LT	170
TOTAL			2,595
USE			2,600

SCHEDULES OF QUANTITIES FOR DETOUR PAVEMENT PATCHING

35800100	
PREPARATION OF BASE	SQ YD
LOCATION	
BRIDGE OVER SPRING CREEK	
# 1	222
# 2	285
N. 1200TH RD.	
# 3	125
# 4	102
E. 700TH RD	
# 5	98
# 6	169
# 7	107
E. 700TH ST.	
# 8	650
INTERSECTION OF CHRISTIAN RD AND E. 750TH ST.	
# 9	440
TOTAL	2,198

35800200		
AGGREGATE BASE REPAIR	DEPTH (IN)	TON
LOCATION		
BRIDGE OVER SPRING CREEK		
# 1	12"	152
# 2	12"	195
N. 1200TH RD.		
# 3	3"	21.5
# 4	8"	47
E. 700TH RD		
# 5	6"	33.5
# 6	6"	58
# 7	6"	56.5
E. 700TH ST.		
# 8	8"	298
INTERSECTION OF CHRISTIAN RD AND E. 750TH ST.		
# 9	3"	75
TOTAL		936.5

40300200	
BIT. MATERIAL (PRIME COAT)	TON
LOCATION	
BRIDGE OVER SPRING CREEK	
# 1	0.44
# 2	0.57
N. 1200TH RD.	
# 3	0.25
# 4	0.2
E. 700TH RD	
# 5	0.2
# 6	0.34
# 7	0.21
E. 700TH ST.	
# 8	1.3
INTERSECTION OF CHRISTIAN RD AND E. 750TH ST.	
# 9	0.88
TOTAL	4.39

1 APPLICATIONS

40300500	
COVER COAT AGGREGATE	TON
LOCATION	
BRIDGE OVER SPRING CREEK	
# 1	5.6
# 2	7.2
N. 1200TH RD.	
# 3	3.2
# 4	2.6
E. 700TH RD	
# 5	2.6
# 6	4.2
# 7	2.6
E. 700TH ST.	
# 8	16.2
INTERSECTION OF CHRISTIAN RD AND E. 750TH ST.	
# 9	11
TOTAL	55.2

2 APPLICATIONS

40300600	
SEAL COAT AGGREGATE	TON
LOCATION	
BRIDGE OVER SPRING CREEK	
# 1	2.8
# 2	3.6
N. 1200TH RD.	
# 3	1.6
# 4	1.3
E. 700TH RD	
# 5	1.3
# 6	2.1
# 7	1.3
E. 700TH ST.	
# 8	8.1
INTERSECTION OF CHRISTIAN RD AND E. 750TH ST.	
# 9	5.5
TOTAL	27.6

1 APPLICATIONS

40300400	
BIT. MAT.(COVER AND SEAL COATS)	TON
LOCATION	
BRIDGE OVER SPRING CREEK	
# 1	1.32
# 2	1.71
N. 1200TH RD.	
# 3	0.75
# 4	0.6
E. 700TH RD	
# 5	0.6
# 6	1.02
# 7	0.63
E. 700TH ST.	
# 8	3.9
INTERSECTION OF CHRISTIAN RD AND E. 750TH ST.	
# 9	2.64
TOTAL	13.17

2 APPLICATIONS - COVER COAT
1 APPLICATION - SEAL COAT