

HOT-MIX ASPHALT SHOULDER TREATMENT, LEFT SIDE								
LOCATION			DISTANCE	SHOULDER	HMA	HMA	HMA SURFACE	HMA SURFACE
			OF RUN	WIDTH	SHOULDERS, 6 1/4" DEPTH	SHOULDERS, 6 1/2" DEPTH	COURSE, 2 1/4" AVG. DEPTH	COURSE, 1 1/2" DEPTH
			(FOOT)	(FOOT)	(SQ YD)	(SQ YD)	(TON)	(TON)
IL RTE. 16 MAINLINE								
STA 100+64.00	TO	STA 102+19.50	155.50	7.00			15.24	
STA 102+19.50	TO	STA 104+06.00	186.50	8.00 to 7.00			19.58	
STA 104+50.00	TO	STA 110+50.00	600.00	4.00	266.67			22.40
STA 110+50.00	TO	STA 116+25.00	575.00	4.00	255.56			21.47
STA 116+25.00	TO	STA 121+75.00	550.00	4.00	244.44			20.53
STA 121+75.00	TO	STA 127+25.00	550.00	4.00	244.44			20.53
STA 127+25.00	TO	STA 131+27.83	402.83	4.00	179.04			15.04
STA. EQUATION: 131+27.83 (BK.) = 131+19.80 (AHD.)								
STA 131+19.80	TO	STA 132+75.00	155.20	4.00	68.98			5.79
STA 132+75.00	TO	STA 138+25.00	550.00	4.00	244.44			20.53
STA 138+25.00	TO	STA 143+75.00	550.00	4.00	244.44			20.53
STA 143+75.00	TO	STA 149+25.00	550.00	4.00	244.44			20.53
STA 149+25.00	TO	STA 154+75.00	550.00	4.00	244.44			20.53
STA 154+75.00	TO	STA 156+47.26	172.26	4.00	76.56			6.43
STA 156+47.26	TO	STA 158+40.49	193.23	7.70			20.83	
WEST FORK SHOAL CREEK								
STA 160+67.70	TO	STA 162+60.32	192.62	7.70			20.76	
STA 162+60.32	TO	STA 165+75.00	314.68	4.00	139.86			11.75
STA 165+75.00	TO	STA 176+75.00	1,100.00	4.00	488.89			41.07
STA 176+75.00	TO	STA 187+75.00	1,100.00	4.00	488.89			41.07
STA 187+75.00	TO	STA 198+75.00	1,100.00	4.00	488.89			41.07
STA 198+75.00	TO	STA 209+75.00	1,100.00	4.00	488.89			41.07
STA 209+75.00	TO	STA 215+77.50	602.50	4.00	267.78			22.49
STA 217+35.00	TO	STA 220+75.00	340.00	4.00	151.11			12.69
STA 220+75.00	TO	STA 231+75.00	1,100.00	4.00	488.89			41.07
STA 231+75.00	TO	STA 242+75.00	1,100.00	4.00	488.89			41.07
STA 242+75.00	TO	STA 242+93.00	18.00	4.00	8.00			0.67
STA 243+32.00	TO	STA 253+75.00	1,043.00	4.00	463.56			38.94
STA 253+75.00	TO	STA 264+75.00	1,100.00	4.00	488.89			41.07
STA 264+75.00	TO	STA 275+25.00	1,050.00	4.00	466.67			39.20
STA 275+25.00	TO	STA 277+75.00	250.00	VARIABLE	190.56			16.00
BRUSH CREEK								
STA 279+56.00	TO	STA 282+20.00	264.00	VARIABLE	195.33			16.41
STA 282+20.00	TO	STA 295+41.50	1,321.50	4.00	587.33			49.36
STA 296+07.50	TO	STA 297+75.00	167.50	4.00	74.44			6.25
STA 297+75.00	TO	STA 308+75.00	1,100.00	4.00	488.89			41.07
STA 308+75.00	TO	STA 319+75.00	1,100.00	4.00	488.89			41.07
STA 319+75.00	TO	STA 330+75.00	1,100.00	4.00	488.89			41.07
STA 330+75.00	TO	STA 336+00.00	525.00	4.00	233.33			19.60
STA 336+00.00	TO	STA 338+50.08	250.08	4.00	111.15			9.34
STA 338+50.08	TO	STA 347+06.35	856.27	4.00		380.56		31.97

SCHEDULE CONTINUED, NEXT SHEET →

-- (15, 21RS-7, 22RS-4, 24RS-8
 --- 42, 325

FILE NAME =	USER NAME = sparksgw	DESIGNED - RTS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et\pwork\p\dot\sparksgw\02222005\0672067-shr-schedule.dgn		DRAWN - RTS	REVISED -		SCALE:	SHEET NO. 6 OF 18 SHEETS	STA.	TO STA.	MONTGOMERY	80	23	
		CHECKED -	REVISED -		CONTRACT NO. 72D67							
		DATE - 04-26-11	REVISED -		ILLINOIS FED. AID PROJECT							