

HOT-MIX ASPHALT SHOULDER TREATMENT, RIGHT SIDE (CONTINUED)								
LOCATION			DISTANCE	SHOULDER	HMA	HMA	HMA SURFACE	HMA SURFACE
			OF RUN	WIDTH	SHOULDERS, 6 1/4" DEPTH	SHOULDERS, 6 1/2" DEPTH	COURSE, 2 1/4" AVG. DEPTH	COURSE, 1 1/2" DEPTH
			(FOOT)	(FOOT)	(SQ YD)	(SQ YD)	(TON)	(TON)
IL RTE.16 / IL RTE. 127 INTERSECTION								
STA 346+75.00	TO	STA 352+25.00	550.00	4.00		244.44		20.53
STA 352+25.00	TO	STA 356+14.76	389.76	4.00		173.23		14.55
STA 356+14.76	TO	STA 365+00.00	885.24	4.00		393.44		33.05
STA 365+00.00	TO	STA 376+00.00	1,100.00	4.00		488.89		41.07
STA 376+00.00	TO	STA 387+00.00	1,100.00	4.00		488.89		41.07
STA 387+00.00	TO	STA 398+00.00	1,100.00	4.00		488.89		41.07
STA 398+00.00	TO	STA 409+00.00	1,100.00	4.00		488.89		41.07
STA 409+00.00	TO	STA 420+00.00	1,100.00	4.00		488.89		41.07
STA 420+00.00	TO	STA 421+71.00	171.00	4.00		76.00		6.38
STA 422+76.00	TO	STA 428+69.55	593.55	4.00		263.80		22.16
STATION EQUATION: 428+69.55 (BK.) = 433+70.11 (AHD.)								
STA 433+70.11	TO	STA 436+50.00	279.89	4.00		124.40		10.45
STA 436+50.00	TO	STA 437+70.00	120.00	4.00		53.33		4.48
STA 437+70.00	TO	STA 440+75.00	305.00	8.00			34.16	
TOTALS:			32,585.26		9,960.10	4,139.71	141.53	1,184.37

-- (15, 21)RS-7, 22RS-4, 24RS-8  
 \*\* 42, 325

FILE NAME =	USER NAME = sparksgw	DESIGNED - RTS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\sparksgw\0222805\0672067-ht-schedule.dgn		DRAWN - RTS	REVISED -					**	.	MONTGOMERY	80	26
PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISIED -			SCALE:	SHEET NO. 9 OF 18 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			
PLOT DATE = Aug-25-2011 10:14:32AM	DATE - 04-26-11	REVISED -			CONTRACT NO. 72D67							