

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				90% FED, 10% STATE
				HIGHWAY LIGHTING
				0021
				URBAN
82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	16.0	16.0
82500360	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 100 AMP	EACH	1.0	1.0
83062730	LIGHT POLE, WEATHERING STEEL, 45 FT. M. H., TENON MOUNT	EACH	16.0	16.0
83600355	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 6'	EACH	16.0	16.0
83800650	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN	EACH	64.0	64.0

FILE NAME :	USER NAME : sparksgu	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pw\work\puidot\sparksgu\0244700\067	BE13-aht-lightingplan.dgn	DRAWN -	REVISED -			310	69-11L-1	MORGAN	17	4	
	PLOT SCALE : 100.0000 / in.	CHECKED -	REVISED -			CONTRACT NO. 72E13		ILLINOIS FED. AID PROJECT			
	PLOT DATE : Oct-20-2011 02:29:33PM	DATE -	REVISED -			SCALE:	SHEET	OF	SHEETS	STA.	TO