

**ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES**

LOCATION OF WORK				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY NHS 80% FED / 20% STATE 0005	BRIDGE REPAIRS NHS 80% FED / 20% STATE 0014 075-0022, -0077, -0080	
20300100	CHANNEL EXCAVATION	CU YD	27	27		
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	17	17		
28100709	STONE DUMPED RIPRAP, CLASS A5	SQ YD	334	334		
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	14	14		
28200200	FILTER FABRIC	SQ YD	360	360		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	133	133		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	67	67		
40600300	AGGREGATE (PRIME COAT)	TON	349	349		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4,433	4,433		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	71	71		
40600990	TEMPORARY RAMP	SQ YD	352	352		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX " C ", N50	TON	14,552	14,552		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	666	666		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1-1/2"	SQ YD	169,522	169,522		
44000300	CURB REMOVAL	FOOT	500	500		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	9	9		
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	473	473		
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	100	100		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3,229	3,229		
50102400	CONCRETE REMOVAL	CU YD	30.3		30.3	
50105220	PIPE CULVERT REMOVAL	FOOT	63	63		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	30.1		30.1	
50300300	PROTECTIVE COAT	SQ YD	69		69	
50400105	PRECAST CONCRETE BRIDGE SLAB	SQ FT	120.0		120.0	

• 104RS2,BR3;105RS7,BR3,4;106RS6

FILE NAME :	USER NAME : sparksgu	DESIGNED :	REVISED :	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\pwwork\sparksgu\d0265393\067	BE*3*skt-500.dgn	DRAWN :	REVISED :			321	-	PIKE	69	3	
	PLOT SCALE : 179.8534 ' / in.	CHECKED :	REVISED :			CONTRACT NO. 72E43		ILLINOIS FED. AID PROJECT			
	PLOT DATE : Oct-31-2011 03:46:22PM	DATE :	REVISED :			SCALE:	SHEET NO. 1 OF 3 SHEETS	STA.	TO STA.		