

**ENTRANCE IMPROVEMENT SCHEDULE FOR RURAL / URBAN "PPP" PROJECT**

LOCATION	TYPE OF ENTRANCE	EX MATERIAL TYPE DRIVE	EX MATERIAL TYPE APRON	LENGTH (FROM EDGE OF PVT/ BIT SHLD TO LIMITS OF IMPROVEMENT)	WIDTH	SHOULDER WIDTH	DRIVEWAY AREA	MAILBOX TURNOUT AREA	TOTAL AREA	PROPOSED HMA THICKNESS	HOT-MIX ASPHALT SURF. REM. BUTT JOINT	PCC SURF. REM. -BUTT JOINT	PREP. OF BASE	AGG. SURFACE COURSE, TYPE B	BIT (PC)	AGG (PC)	INCIDENTAL HOT-MIX ASPHALT SURFACING
( LT / RT ) STA	( FE/PE/CE/MB ) ( RURAL/URBAN )	( EARTH/AGG. / O&C/BIT. /PCC )	( EARTH/AGG. / O&C/BIT. /P. C. C )	FOOT	FOOT	FOOT	SQ. FT.	SQ. FT.	SQ. FT.	INCH	SQ. YD.	SQ. YD.	SQ. YD.	TON	TON	TON	TON
LT STA. 180+10	FE / RURAL	AGG	BIT	8	12	4	120	0	120	1.5	13.3			1	0.01	0.03	2.00
RT STA. 180+60	FE / RURAL	AGG	BIT	8	12	4	120	113	233	1.5	25.9			1	0.01	0.05	3.00
LT STA. 181+70	PE / RURAL	AGG	BIT	8	24	4	168	0	168	1.5	18.7			2	0.01	0.04	2.00
RT STA. 190+40	PE / RURAL	AGG	BIT	8	24	4	168	84	252	1.5	28.0			2	0.01	0.06	3.00
LT STA. 192+60	FE / RURAL	AGG	BIT	8	12	4	120	0	120	1.5	13.3			1	0.01	0.03	2.00
LT STA. 200+75	FE / RURAL	AGG	BIT	8	12	4	120	0	120	1.5	13.3			1	0.01	0.03	2.00
RT STA. 200+75	FE / RURAL	AGG	BIT	8	12	4	120	0	120	1.5	13.3			1	0.01	0.03	2.00
LT STA. 207+18	FE / RURAL	AGG	BIT	8	12	4	120	0	120	1.5	13.3			1	0.01	0.03	2.00
RT STA. 208+00	PE / RURAL	AGG	BIT	8	14	4	128	100	228	1.5	25.3			1	0.01	0.05	3.00
RT STA. 209+85	PE / RURAL	AGG	BIT	8	12	4	120	0	120	1.5	13.3			1	0.01	0.03	2.00
LT STA. 217+00	FE / RURAL	AGG	BIT	8	12	4	120	0	120	1.5	13.3			1	0.01	0.03	2.00
RT STA. 217+00	FE / RURAL	AGG	BIT	8	12	4	120	0	120	1.5	13.3			1	0.01	0.03	2.00
RT STA. 226+85	PE / RURAL	AGG	BIT	8	16	4	136	100	236	1.5	26.2			1	0.01	0.05	3.00
LT STA. 255+00	PE / RURAL	AGG	BIT	8	24	4	168	0	168	1.5	18.7			2	0.01	0.04	2.00
RT STA. 255+10	PE / RURAL	AGG	BIT	8	24	4	168	0	168	1.5	18.7			2	0.01	0.04	2.00
RT STA. 267+20	FE / RURAL	AGG	BIT	8	12	4	120	0	120	1.5	13.3			1	0.01	0.03	2.00
RT STA 272+95	FE / RURAL	AGG	BIT	8	12	4	120	0	120	1.5	13.3			1	0.01	0.03	2.00
RT STA. 277+60	PE / RURAL	AGG	BIT	8	20	4	152	100	252	1.5	28.0			1	0.01	0.06	3.00
RT STA. 281+80	PE / RURAL	AGG	BIT	8	20	4	152	0	152	1.5	16.9			1	0.01	0.03	2.00
LT STA. 282+85	FE / RURAL	AGG	BIT	8	24	4	168	0	168	1.5	18.7			1	0.01	0.04	2.00
LT STA. 292+80	FE / RURAL	AGG	BIT	8	12	4	120	0	120	1.5	13.3			1	0.01	0.03	2.00
RT STA. 295+55	PE / RURAL	AGG	BIT	8	24	4	168	100	268	1.5	29.8			2	0.01	0.06	3.00
RT STA 297+30	PE / RURAL	AGG	BIT	8	24	4	168	0	168	1.5	18.7			2	0.01	0.04	2.00
RT STA. 298+80	PE / RURAL	AGG	BIT	8	16	4	136	0	136	1.5	15.1			1	0.01	0.03	2.00
RT STA. 341+05	CE / RURAL	AGG	BIT	10	35	0	550	203	753	1.5	83.6			1	0.03	0.17	8.00
LT STA. 341+65	PE / RURAL	AGG	AGG	8	24	0	368	0	368	3.5	0.0			2	0.02	0.08	9.00
LT STA. 343+80	CE / RURAL	AGG	BIT	10	24	0	440	0	440	1.5	48.9			1	0.02	0.10	5.00
LT STA. 344+75	CE / RURAL	PCC	PCC	10	35	0	550	0	550	1.5	0.0	61.1		0	0.02	0.12	6.00
LT STA. 346+40	PE / RURAL	AGG	AGG	8	14	0	288	0	288	3.5	0.0			1	0.01	0.06	7.00
LT STA. 347+55	PE / RURAL	AGG	AGG	8	12	0	272	0	272	3.5	0.0			1	0.01	0.06	6.00
RT STA. 348+10	MB / RURAL	BIT	BIT				0	346	346	1.5	38.4			0	0.01	0.08	4.00
LT STA. 349+20	CE / RURAL	AGG	AGG	10	24	0	440	0	440	8	0.0			1	0.02	0.10	22.00
LT STA. 349+65	CE / RURAL	AGG	AGG	10	24	0	440	0	440	8	0.0			1	0.02	0.10	22.00
RT STA. 351+30	PE / RURAL	AGG	PCC	8	12	5	87	0	87	1.5	0.0	9.7		1	0.00	0.02	1.00

• 104RS2,BR3;105RS7,BR3,4;106RS6

FILE NAME =	USER NAME = sparksgw	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pw\work\p\idot\sparksgw\10265393\067E43-sht-schedule.dgn	DRAWN -	REVISED -	321					*	PIKE	69	10	
PLOT SCALE = 106.7353' / in.	CHECKED -	REVISED -	CONTRACT NO. 72E43									
PLOT DATE = Oct-31-2011 03:58:40PM	DATE -	REVISED -	SCALE:		SHEET NO. 5 OF 8 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				