



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 10, 2012

SUBJECT: FAP Route 823 (IL 15)
Project F-BRF-0823 (012)
Section (22, B2A)B-1 & (22, B2B)B-1
Wayne County
Contract No. 74216
Item No. 152, January 20, 2012 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised sheets 3 and 85 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Roger Driskell, Region 4, District 7; Mike Renner; D.Carl Puzey;
Estimates

TBW:DB:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 74216

State Job # - C-97-004-07
 PPS NBR - 7-83010-0000
 County Name - WAYNE- -
 Code - 191 - -
 District - 7 - -
 Section Number - (22,B2A)B-1 & (22,B2B)B-1

Project Number
 F-BRF-0823/012/

Route
 FAP 823

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X2070304	POROUS GRAN EMB SPEC	CU YD	198.000				
X2501000	SEEDING CL 2 SPL	ACRE	1.000				
X5030270	BR DK SHRNK COMP CONC	CU YD	246.600				
Z0026407	TEMP SHT PILING	SQ FT	1,090.000				
Z0030250	IMP ATTN TEMP NRD TL3	EACH	4.000				
Z0030350	IMP ATTN REL NRD TL3	EACH	4.000				
Z0046304	P UNDR FOR STRUCT 4	FOOT	285.000				
Z0076600	TRAINEES	HOUR	500.000		0.800		400.000
20200100	EARTH EXCAVATION	CU YD	366.000				
20300100	CHANNEL EXCAVATION	CU YD	1,131.000				
20400800	FURNISHED EXCAVATION	CU YD	1,066.000				
28000250	TEMP EROS CONTR SEED	POUND	260.000				
28000400	PERIMETER EROS BAR	FOOT	3,256.000				
28000500	INLET & PIPE PROTECT	EACH	8.000				
28100107	STONE RIPRAP CL A4	SQ YD	2,045.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 74216

State Job # - C-97-004-07
 PPS NBR - 7-83010-0000
 County Name - WAYNE -
 Code - 191 - -
 District - 7 - -
 Section Number - (22,B2A)B-1 & (22,B2B)B-1

Project Number
 F-BRF-0823/012/

Route
 FAP 823

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
28200200	FILTER FABRIC	SQ YD	2,045.000				
35400500	PCC BASE CSE W 10	SQ YD	748.000				
*REV 40600100	BIT MATLS PR CT	GALLON	251.000				
40600982	HMA SURF REM BUTT JT	SQ YD	1,203.000				
40600990	TEMPORARY RAMP	SQ YD	124.000				
*REV 40603085	HMA BC IL-19.0 N70	TON	678.000				
*REV 40603315	HMA SC "C" N70	TON	263.000				
42001430	BR APPR PVT CON (FLX)	SQ YD	66.000				
44000151	HMA SURF REM 1/2	SQ YD	2,380.000				
44004250	PAVED SHLD REMOVAL	SQ YD	297.000				
48203029	HMA SHOULDERS 8	SQ YD	625.000				
48203037	HMA SHOULDERS 10	SQ YD	505.000				
48203100	HMA SHOULDERS	TON	220.000				
50100300	REM EXIST STRUCT N1	EACH	1.000				
50100400	REM EXIST STRUCT N2	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 74216

State Job # - C-97-004-07
 PPS NBR - 7-83010-0000
 County Name - WAYNE -
 Code - 191 - -
 District - 7 - -
 Section Number - (22,B2A)B-1 & (22,B2B)B-1

Project Number
 F-BRF-0823/012/

Route
 FAP 823

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50200100	STRUCTURE EXCAVATION	CU YD	337.600				
50200300	COFFERDAM EXCAVATION	CU YD	452.400				
50201101	COFFERDAM TYP 1 LOC 1	EACH	1.000				
50201102	COFFERDAM TYP 1 LOC 2	EACH	1.000				
50201103	COFFERDAM TYP 1 LOC 3	EACH	1.000				
50201104	COFFERDAM TYP 1 LOC 4	EACH	1.000				
50300100	FLOOR DRAINS	EACH	32.000				
50300225	CONC STRUCT	CU YD	431.700				
50300255	CONC SUP-STR	CU YD	339.000				
50300260	BR DECK GROOVING	SQ YD	911.000				
50300280	CONCRETE ENCASEMENT	CU YD	37.200				
50300300	PROTECTIVE COAT	SQ YD	1,752.200				
50400805	F & E P P CON I-BM 36	FOOT	916.000				
50500105	F & E STRUCT STEEL	L SUM	1.000				
50500505	STUD SHEAR CONNECTORS	EACH	2,772.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 74216

State Job # - C-97-004-07
 PPS NBR - 7-83010-0000
 County Name - WAYNE- -
 Code - 191 - -
 District - 7 - -
 Section Number - (22,B2A)B-1 & (22,B2B)B-1

Project Number
 F-BRF-0823/012/

Route
 FAP 823

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50800205	REINF BARS, EPOXY CTD	POUND	175,110.000				
50800515	BAR SPLICERS	EACH	1,630.000				
50800530	MECHANICAL SPLICERS	EACH	168.000				
51201800	FUR STL PILE HP14X73	FOOT	1,392.000				
51202100	FUR STL PILE HP14X117	FOOT	2,665.000				
51202305	DRIVING PILES	FOOT	4,057.000				
51203800	TEST PILE ST HP14X73	EACH	4.000				
51204100	TEST PILE ST HP14X117	EACH	4.000				
51500100	NAME PLATES	EACH	2.000				
52000110	PREF JT STRIP SEAL	FOOT	83.000				
52100010	ELAST BEARING ASSY T1	EACH	12.000				
52100020	ELAST BEARING ASSY T2	EACH	6.000				
52100520	ANCHOR BOLTS 1	EACH	48.000				
58700300	CONCRETE SEALER	SQ FT	842.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	117.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 74216

State Job # - C-97-004-07
 PPS NBR - 7-83010-0000
 County Name - WAYNE -
 Code - 191 - -
 District - 7 - -
 Section Number - (22,B2A)B-1 & (22,B2B)B-1

Project Number
 F-BRF-0823/012/

Route
 FAP 823

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60100060	CONC HDWL FOR P DRAIN	EACH	8.000				
60100905	PIPE DRAINS 4	FOOT	240.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	800.000				
63100085	TRAF BAR TERM T6	EACH	8.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	8.000				
63200310	GUARDRAIL REMOV	FOOT	1,549.000				
66700305	PERM SURV MKRS T2	EACH	2.000				
67000400	ENGR FIELD OFFICE A	CAL MO	12.000				
67100100	MOBILIZATION	L SUM	1.000				
70100405	TRAF CONT-PROT 701321	EACH	2.000				
70100460	TRAF CONT-PROT 701306	L SUM	1.000				
70100500	TRAF CONT-PROT 701326	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	4.000				
70106500	TEMP BR TRAF SIGNALS	EACH	2.000				
70106700	TEMP RUMBLE STRIPS	EACH	12.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 74216

State Job # - C-97-004-07
 PPS NBR - 7-83010-0000
 County Name - WAYNE - -
 Code - 191 - -
 District - 7 - -
 Section Number - (22,B2A)B-1 & (22,B2B)B-1

Project Number
 F-BRF-0823/012/

Route
 FAP 823

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70300100	SHORT TERM PAVT MKING	FOOT	248.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	2,417.000				
70400100	TEMP CONC BARRIER	FOOT	1,459.000				
70400200	REL TEMP CONC BARRIER	FOOT	1,421.000				
78001110	PAINT PVT MK LINE 4	FOOT	3,708.000				
78100100	RAISED REFL PAVT MKR	EACH	39.000				
78100105	RAISED REF PVT MKR BR	EACH	10.000				
78200410	GUARDRAIL MKR TYPE A	EACH	40.000				
78201000	TERMINAL MARKER - DA	EACH	8.000				
78300100	PAVT MARKING REMOVAL	SQ FT	1,236.000				