

PAVEMENT MARKING & SHORT TERM PAVEMENT MARKING

STATION	TO	STATION	SIDE	PAINT PVMT MARKING		SHORT TERM PM		REMARKS
				WHITE 4"	YELLOW 4"	FOOT	FOOT	
399+50.00		405+95.00	LT	645		52		EDGE LINE
399+50.00		405+95.00	RT	645		52		EDGE LINE
399+50.00		405+95.00	RT		258	0		SKIP
TOTAL				1290	258	104		

PCC BASE COURSE WIDENING

STATION	TO	STATION	SIDE	PCC BASE CSE WIDENING 10"	
				FOOT	SQ YD
399+50.00		402+25.10	RT		148
399+50.00		400+85.60	LT		23
403+16.60		405+05.20	RT		104
404+29.80		405+95.00	LT		28
405+05.20		405+26.90	RT		9
405+26.90		405+95.00	RT		11
TOTAL					323

TEMPORARY PAVEMENT MARKING ***

STATION	TO	STATION	STAGE		
			WHITE 4"	WHITE 4"	WHITE 24"
395+14.50					12.5
395+74.60		406+97.70	825		
399+86.50		40526.5	540.8		
398+24.50		406+47.80		824.9	
399+53.00		405+49.50		596.2	
407+07.70					12.5
TOTAL			1365	1421	25

PAVEMENT MARKING REMOVAL

STATION	TO	STATION	PM REM SQ FT
399+50.00		405+95.00	215
399+50.00		405+95.00	215
399+50.00		405+95.00	86
TOTAL			516

HOT-MIX ASPHALT

STATION	TO	STATION	HMA SURFACE		BIT MATERIALS ON HMA	
			TON	TON	GAL	GAL
399+50.00		401+84.50	55		53	
400+67.10		401+84.50		60		
BRIDGE OMISSION						
403+75.50		404+60.90		44		
403+75.50		405+95.00	52		49	
TOTAL			107	104	102	

PAVED SHOULDER REMOVAL

STATION	TO	STATION	SIDE	PAVED SHOULDER REMOVAL	
				FOOT	SQ YD
399+50.00		402+25.10	RT		51
399+50.00		400+85.60	LT		17
403+18.70		405+95.00	RT		57
404+29.80		405+95.00	LT		19
TOTAL					144

WORK ZONE PVMT MARKING REMOVAL

STATION	TO	STATION	STAGE		
			WHITE 4"	WHITE 4"	WHITE 24"
395+14.50					25
395+74.60		406+97.70	275		
399+86.50		405+26.50	180		
398+24.50		406+47.80		275	
399+53.00		405+49.50		199	
407+07.70		0+00.00			25
TOTAL			455	474	50

HMA SHOULDERS

STATION	TO	STATION	SIDE	HMA SHOULDERS		BIT MATERIALS ON HMA	
				8" SQ YD	10" SQ YD	TON	GAL
399+50.00		401+99.40	LT		110		1.0
399+99.20		402+01.90	LT	64			0.6
399+50.00		401+82.10	RT			47	0.0
399+74.20		401+79.10	RT	66			0.6
BRIDGE OMISSION							
403+57.80		405+62.70	RT	66			0.6
403+58.00		405+95.00	RT			48	0.0
403+78.60		405+95.00	LT		95		0.9
403+81.20		405+85.10	LT	67			0.6
TOTAL				263	205	95	5

*** INCLUDED FOR CONTRACTOR INFORMATION ONLY. COST TO BE INCLUDED WITH TRAFFIC CONTROL AND PROTECTION, (SPECIAL).

PRINTED DATE: 12/15/2011
FILE NAME: c:\pva\projects\148\1.com 25 - 07\various design\work_order_06\cadd\pva\worksheets\07_W06_SCH02.dgn



USER NAME = #USER#
PLOT SCALE = 1:10000' / IN.
PLOT DATE = 12/15/2011

DESIGNED -
DRAWN -
CHECKED -
DATE - 3-23-2011

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SN: 096-0074
SCHEDULES**

SHEET NO 2 OF 2 SHEETS

F.A.P. RTE 823

SECTION (22.B2A)B-1 & (22.B2B)B-1

COUNTY WAYNE
TOTAL SHEETS 85
SHEET NO 7

ILLINOIS FEDERAL AID PROJECT

CONTRACT NO 74216