PAVEMENT MARKING & SHORT TERM PAVEMENT MARKING

STATION	TO	STATION	SIDE	PAINT PVMT MARKING WHITE 4" FOOT	PAINT PVMT MARKING YELLOW 4" FOOT	SHORT TERM PM FOOT	REMARKS
424+30.00		433+30.00	LT	900		72	EDGE LINE
424+30.00		433+30.00	RT	900		72	EDGE LINE
424+30.00		433+30.00	RT		360	0	SKIP
TOTAL				1800	360	144	

HOT-MIX ASPHALT

STATION	TO	STATION	HMA SURFACE TON	HMA BINDER TON	BIT MATERIALS ON HMA GAL
424+30.00		427+64.80	704		53
425+21.60		427+70.60		2562	
BRIDGE OMISSION					
429+87.20		432+39.70		2600	
429+93.20		433+30.00	708		49
TOTAL			1412	5162	102

HMA SHOULDERS

STATION	TO	STATION	SIDE	8" SQ YD	10" SQ YD	HMA SHOULDERS TON	BIT MATERIALS ON HMA GAL
424+30.00		427+80.30	LT		153		1.4
425+66.70		427+80.80	LT	71			0.7
424+30.00		425+21.60	RT	40			0.4
425+21.60		427+63.20	RT			60	0.0
425+48.60		427+60.70	RT	70			0.7
BRIDGE OMISSION							
429+77.50		431+91.60	RT	71			0.7
429+78.90		432+39.70	RT			65	0.0
432+39.70		433+30.00	RT	40			0.4
429+94.10		433+30.00	LT		147		1.4
429+97.00		432+09.90	LT	70			0.7
TOTAL				362	300	125	7

PCC BASE COURSE WIDENING

STATION	TO	STATION	SIDE	PCC BASE CSE WIDENING 10" SQ YD
424+20.30		424+45.80	RT	11
424+30.00		425+51.40	LT	20
424+45.80		428+05.30	RT	177
429+38.80		433+27.60	RT	189
432+10.60		433+30.00	LT	20
433+27.60		433+49.20	RT	8
TOTAL				425

PAVED SHOULDER REMOVAL

STATION	TO	STATION	SIDE	PAVED SHOULDER REMOVAL SQ YD
424+20.30		428+04.30	RT	58
424+30.00		425+51.40	LT	15
429+40.50		433+49.20	RT	63
432+10.60		433+30.00	LT	17
TOTAL				153

TEMPORARY PAVEMENT MARKING ***

STATION	TO	STATION	STAGE I WHITE 4" FOOT	STAGE II WHITE 4" FOOT	WHITE 24" FOOT
422+52.10					12.5
423+12.30		434+69.10	1158		
424+20.30		43349.1	928		
422+62.20		434+34.40		1174	
424+27.50		433+31.20		905	
434+94.40					12.5
TOTAL			2086	2079	25

*** INCLUDED FOR CONTRACTOR INFORMATION ONLY. COST TO BE INCLUDED WITH TRAFFIC CONTROL AND PROTECTION, (SPECIAL).

WORK ZONE PVMT MARKING REMOVAL

STATION	TO	STATION	STAGE I WHITE 4" SQ FT	STAGE II WHITE 4" SQ FT	WHITE 24" SQ FT
422+52.10					25
423+12.30		434+69.10	386		
424+20.30		433+49.10	309		
422+62.20		434+34.40		391	
424+27.50		433+31.20		302	
434+94.40		0+00.00			25
TOTAL			695	693	50

PAVEMENT MARKING REMOVAL

STATION	TO	STATION	PM REM SQ FT
424+30.00		433+30.00	300
424+30.00		433+30.00	300
424+30.00		433+30.00	120
			720